

The Currency Leg of a Knock-Out Oil Option under Jump-Diffusion: Factorization, Netting, and What a Fitted LSMC Delta Does Not Buy

Jihong Park

Pusan National University

adrianus026@gmail.com

July 2026

Abstract

A Korean crude-oil importer hedging joint WTI and USD/KRW exposure with a barrier oil option settled in won must decide how to size the currency leg. A change of numeraire shows that this payoff factorizes into the spot rate times a pure dollar option, so the correlation desks associate with such structures enters neither its price nor either of its deltas, and the structure's entire currency exposure is its own carrying value per unit of the exchange rate. That is the paper's positive result and it is exact.

The rest is a set of negative results about the estimator such structures are usually hedged with, each obtained by controlling something the original comparison did not. A fitted least-squares Monte Carlo surface delta, examined across its own fitted domain, is close to a constant: it spans 0.033 where a Black-76 delta spans 0.36, it never reproduces the sign reversal an up-and-out call carries near knock-out, and it is rank-deficient at inception. Its apparent hedging advantage over a barrier-blind delta is reproduced in full by a constant hedge ratio with no fitting and no barrier information, so the advantage belongs to the level of the ratio and not to barrier awareness. Once the ledger stops where the American price says the contract stops, rather than running to maturity against an American premium, the comparison reverses outright and the closed-form delta is the better hedge. And the variance-minimizing coupling multiplier the coupled family defines is not a covariance-aware hedge ratio but a bookkeeping correction: netting the currency exposure that the oil futures leg already carries moves the minimizer by exactly one unit and leaves nothing economically distinguishable from zero.

The practical recommendation is unchanged and is now reached more directly: size the currency leg to the option's own carrying value, net of what the oil leg already carries, and test any claim that a fitted surface delivers barrier-aware hedging against a constant-delta control before accepting it.

Keywords: delta hedging; barrier option; knock-out; jump-diffusion; least-squares Monte Carlo; minimum-variance hedge ratio; currency risk

JEL classification: G13; G32; C63; Q40

Contents

1	Introduction	4
2	Literature Review	6
3	Asset Dynamics and P/Q Separation	8
3.1	Two-Asset Correlated Jump-Diffusion SDE	8
3.2	Quanto Double-Knock-Out Payoff Construction	10
3.3	Orthogonal Girsanov Transform and Risk Premium Isolation	11
4	Calibration of WTI Jump/Diffusion Inputs	12
4.1	Asymmetric Up/Down Jump Decomposition	12
5	Numerical Model Formulation	13
5.1	Path Simulation and the Longstaff—Schwartz Backward-Induction Algorithm . .	13
5.2	Corrected State-Variable Normalization and the 5-Term Polynomial Basis	14
5.3	The Closed-Form LSMC Regression Delta	15
5.4	Log-Space Brownian Bridge Barrier Correction: Upper and Lower Barriers . . .	16
6	Empirical Results	17
6.1	Baseline Pricing and the Knock-Out Rate	17
6.2	Hedge Cost: American LSMC vs. Closed-Form Proxies	17
6.3	Decomposing the Gap: The Contribution of the Delta Rule	19
6.4	The comparison under a consistent ledger	21
6.5	Empirical Total-P&L Distribution vs. a Fitted Normal	21
6.6	Alive-and-In-the-Money Path Density	23
7	Sensitivity Studies	23
7.1	Finite-Difference vs. Regression Delta	23
7.2	State Dependence of the Fitted Surface	25
7.3	Hedge-Cost Sensitivity to the FX Coupling Multiplier	25
7.4	From sweep to minimizer: the closed-form optimal multiplier	27
7.5	What the FX delta should be: the structure’s own analytic sensitivity	28
7.6	Jump Risk-Premium Re-Pricing Sensitivity	30
7.7	Jump-Threshold Calibration Robustness	31
8	Model Validation and Robustness	32
8.1	Exact Validation: Closed-Form Drift Bias	32
8.2	Inexact Validation: Reweighting the Actual Barrier Payoff	32
8.3	Exact Simulation, Error Decomposition, and Convergence	34
8.3.1	The jump-gap residual, measured	34
8.3.2	Error decomposition and convergence	34
8.3.3	A dual upper bound: the exercise policy is near-optimal	35
8.3.4	Esscher-consistent jump risk premium	35

8.3.5	What survives, and what changes, at 200,000 exact paths	35
9	Discussion	36
10	Limitations	37
11	Conclusion	38
A	Convergence and Basis-Robustness Tables	39
B	Proof of the American Extension of Proposition 1	40
C	The Jump-Classification and Moment-Matching Construction	40

1 Introduction

Korean refiners and independent crude-oil importers hold a joint exposure to two only weakly correlated risk factors: the US-dollar price of WTI crude, and the USD/KRW exchange rate that converts that dollar liability into the importer’s home-currency cash outflow. Left unhedged, a firm with a fixed monthly physical oil requirement (in the production configuration studied here, 2,000,000 barrels per month, equivalently a USD funding need of \$157,880,000 per month) is simultaneously short WTI and short KRW (long USD) in a way that a single-asset hedge cannot address. The natural instrument is a two-asset, quanto-style structure whose payoff is linear in both S_1 (WTI) and S_2 (USD/KRW), typically embedded with a double knock-out (KO) barrier to reduce premium: in the specification studied here, KO triggers if WTI trades above 120 or below 50 USD/bbl at any point before maturity.

A remark on instrument choice is due up front. The industry-standard hedge for this exposure is the zero-cost collar, a purchased cap financed by a written floor and familiar from refiner and airline hedging programs, whose payoff is continuous and whose delta hedging is textbook. The double-KO quanto is studied here because it is the instrument on which per-asset delta estimation actually breaks, through a discontinuous payoff, path dependence, jump risk, and a second correlated leg, so it is where a covariance-aware hedge ratio has research content and not being a corollary of Black-76. Nothing in the method is specific to the exotic; applied to a collar it collapses to the classical continuous-delta case, which is precisely why the collar is not the object of study.

The portfolio-optimal static split of the hedging budget between the WTI leg and the FX leg, a one-shot allocation decision made at inception, lies outside this paper’s target. This paper’s target is how the FX leg’s hedge ratio should be set once the two legs’ risks are coupled by the structure itself, through the shared knock-out barrier, the jump component, and the cross-asset correlation, and not each delta being estimated independently, asset by asset. The natural reference point for an independent, per-asset treatment is the one-parameter family $\delta_{FX}(t) = c \cdot \delta_{WTI}(t)$ evaluated at $c = 1.0$, i.e. full one-for-one pass-through of the WTI hedge notional into the FX leg, the simplest rule available when the FX leg’s own risk profile is not separately modeled. This paper asks two questions of that family, and one question outside it entirely: what the covariance between the two legs’ hedge costs implies for the coupling parameter c ; and, independent of any coupled family at all, what the structure’s own analytic sensitivity to the FX rate implies the FX delta should be. The answer to the first depends in turn on how reliably $\delta_{WTI}(t)$ itself can be estimated once the option carries a discrete, path-dependent knock-out feature that no closed-form pricing model represents exactly, since any coupling to δ_{WTI} transmits every WTI-delta error directly into the FX leg.

No existing strand of the literature supplies a covariance-aware FX hedge ratio for this specific setting. The cross-hedging literature descending from Anderson—Danthine treats *static* hedge ratios on futures, not the dynamic delta coupling of an option position rebalanced daily; the quanto-pricing literature derives correlation drift adjustments for *valuation* but stops short of the two-legged operational hedging problem a desk actually runs; and the barrier-option hedging literature concentrates on the discontinuity at the barrier of a single underlying, not on how a second, correlated currency leg’s hedge ratio should be set jointly with the first. This

paper fills that gap directly. The contributions are: (i) a measured, common-random-number comparison of three delta-estimation methods (LSMC regression, Black-76 proxy, Turnbull—Wakeman proxy) on an identical path bank, together with the controls, a common ledger, a constant-delta rule, and an exercise-consistent stopping time, that decompose the raw gap and reverse its attribution; (ii) an exact per-path affine decomposition of hedge cost in the coupling parameter c (Section 7.3), showing hedge-cost variance is an exact parabola in c , which is used here not to endorse its vertex as a hedge ratio but to locate and explain that vertex; (iii) a diagnosis of the variance-minimizing coupling multiplier $c^* = -\text{Cov}(A, B)/\text{Var}(B)$ that this structure’s affine hedge-cost decomposition defines: the multiplier is real as an identity but not as economics, because on the shipped ledger it is dominated by an unintended currency position the oil futures leg already carries, and netting that position collapses the multiplier to zero (Section 7.4); (iv) a corollary of that factorization giving the structure’s own analytic FX delta as $V(t)/S_2(t)$, the option’s carrying value, and a measured $4.6\times$ gap against the coupled family’s reference point (Section 7.5); (v) a decomposition of the KO-rate statistic showing the American engine’s lower reported KO rate reflects early-exercise pre-emption and not a different barrier process; and (vi) a numerical-rigor layer (jump-adapted exact path simulation with exact first-passage barrier treatment, an Esscher-consistent jump risk-premium transformation, basis-robustness and convergence studies, and dual upper-bound pricing diagnostics) that removes the discretization component of simulation error from the reported numbers and quantifies what remains (Section 8.3). This layer addresses numerical error only; the estimation uncertainty in the calibrated inputs is a separate and larger source of dispersion, and is discussed in Section 10.

Figure 1 shows the historical WTI and USD/KRW series underlying the calibration of Section 4: 1,301 paired daily closes spanning 28 June 2021 to 22 June 2026, which difference to the 1,300 paired daily log returns that constitute the estimation sample used throughout (Section 4), over which WTI alone ranges from below \$60 to above \$100 per barrel and USD/KRW moves from roughly 1,130 to above 1,600, indicating the joint magnitude of commodity and currency risk this structure is built to address.




Figure 1: Historical WTI spot and USD/KRW, the calibration source series (Section 4).

The structural difficulty is this: the KO feature destroys the applicability of the text-

book closed-form models (Black-76 for the European vanilla proxy, Turnbull—Wakeman for the Asian-averaging proxy) that a practitioner would otherwise reach for first, because neither model has a barrier term in its analytic derivation. A Longstaff—Schwartz least-squares Monte Carlo (LSMC) regression, by contrast, prices and differentiates the option *on the same simulated paths that determine the KO event*, so the barrier is handled within the same numerical machinery that produces the hedge ratio. This paper’s central empirical exercise is to test that presumption rather than assume it. On an identical common-random-number path bank, so that all three delta-estimation methods see the same realized KO/no-KO outcome, the raw comparison indeed favors the regression surface by an order of magnitude. The paper then adds one control at a time and the advantage does not survive the controls: holding contract, premium and stopping rule fixed shrinks it to 12% (Section 6.3); a constant hedge ratio with no barrier information reproduces what remains; and stopping the ledger where the American price says the contract stops reverses the sign outright, leaving the barrier-blind proxy the better hedge on this structure (Section 6.4). The measured result is a caution about the estimator, not a vindication of it.

The remainder of the paper is organized as follows. Section 2 places the model in the existing literature. Section 3 derives the correlated jump-diffusion dynamics, the quanto double-barrier payoff, and the orthogonal Girsanov transform used to move between the physical measure $\mathbb{P}$ and the pricing measure $\mathbb{Q}$. Section 4 documents the calibration of the WTI jump/diffusion parameters from historical data and the variance-decomposition hazard this creates. Section 5 gives the full numerical formulation: the Longstaff—Schwartz backward-induction algorithm, the corrected 5-term regression basis, the closed-form regression delta, and the log-space Brownian bridge barrier correction. Section 6 reports the empirical baseline results. Section 7 reports sensitivity studies. Section 8 validates the model and the numerical scheme together: the P/Q measure separation directly against simulation, then the scheme’s approximation layers removed entirely via a jump-adapted exact simulation at 200,000 paths, with measured error decomposition, convergence, a dual price bound, and an Esscher-consistent risk-premium tilt. Section 9 discusses the central technical tension the results expose. Section 10 catalogs the model’s limitations, and Section 11 concludes.

2 Literature Review

The theoretical foundation for the jump-diffusion dynamics used throughout is Merton (1976), who first formalized a diffusion process punctuated by a compound Poisson jump component and showed that, because jump risk cannot be spanned by continuously-traded instruments, the resulting market is incomplete. Longstaff and Schwartz (2001) supply the numerical engine: least-squares regression of the discounted continuation value onto a low-order polynomial basis of the state variables, evaluated only on in-the-money paths, which turns the pricing of an American-style (or any early-exercise or path-dependent) claim into a tractable backward-induction regression problem. This paper’s American engine is a direct, KO-barrier-augmented application of that method; its Asian engine likewise migrates to the same LSMC regression machinery specifically because the KO barrier cannot be represented in a closed-form Asian

pricing model.

Two closed-form benchmarks are used explicitly as proxies against which the regression delta is compared. Black (1976) supplies the forward-based closed-form option price used for the European vanilla proxy leg; Turnbull and Wakeman (1991) supply the moment-matching closed-form approximation for the arithmetic-average Asian proxy leg. Neither model has any mechanism to represent a discrete monitored barrier, which is precisely the property this paper exploits: both are deliberately used *as if* they were adequate for a KO structure, so that the resulting hedging degradation can be measured and not merely asserted. Finally, Garman and Kohlhagen (1983) supplies the closed-form FX option formula used wherever a standalone currency option valuation is required in the surrounding sensitivity and diagnostic machinery (in particular the FX leg’s own delta terms feeding the one-for-one coupling $\delta_{FX} = \delta_{WTI}$ that the reference point $c = 1$ imposes). The correlation coupling between the two legs is priced here as Reiner (1992) characterizes it, as a genuine quanto drift adjustment, but recovered by joint correlated simulation and not by applying his closed-form adjustment directly, for a simple reason: no closed form of that kind survives the addition of a discretely monitored double barrier.

The discrete-monitoring barrier correction used throughout (Section 5.4) is not derived from first principles here; it is the continuity correction of Broadie, Glasserman, and Kou (1997), who show that a barrier monitored at n discrete dates can be priced, to a good approximation, by shifting the barrier by $\pm\beta\sigma\sqrt{\Delta t}$ and applying the continuous-monitoring formula, or, as implemented in this paper’s regression engine, by a direct Brownian-bridge touch-probability test on each discretization interval. The contribution here is the correction’s integration into an LSMC regression pipeline for a two-asset quanto structure, and the direct measurement, in Section 8.3.1, of the residual gap the correction leaves against jump risk it was not designed to see.

The jump-diffusion literature’s central structural consequence, market incompleteness under discontinuous trajectories, is the reason a diversifiable jump-risk premium survives the $\mathbb{P} \rightarrow \mathbb{Q}$ transition in the pricing measure used here (Section 3.3), consistent with the incomplete-markets treatment of jump-diffusion hedging in Cont and Tankov (2004). It is also the direct cause of the finite-difference/regression-delta divergence documented empirically in Section 7.1: Broadie and Glasserman (1996) establish, for simulation-based Greeks generally, that pathwise and finite-difference estimators can diverge sharply for payoffs with discontinuities of this kind, and a regression fitted on a polynomial basis over a finite, discretely-jumping path set inherits the same structural difficulty and not escaping it. Section 7.1 accordingly measures the magnitude of this known phenomenon on the specific barrier-quanto structure studied here.

What none of these strands directly supplies is a covariance-aware hedge ratio for two legs coupled through a shared barrier and a shared jump component, and not through a simple linear correlation in continuous-time diffusion alone. The cross-hedging tradition of Anderson and Danthine (1981) and its currency extension in Adler and Dumas (1984) optimizes *static* hedge ratios for futures positions, a single number chosen once, and has no object corresponding to a delta recomputed daily on an option whose barrier can extinguish it; its optimality conditions do not speak to a coupling rule applied at every rebalancing date. The unconstrained, single-

period version of that same optimization is the minimum-variance hedge ratio of Ederington (1979), and the affine per-path cost decomposition of Section 7.4 writes this structure’s hedge-cost variance as an exact parabola in the coupling parameter whose vertex is that classical ratio. What Section 7.4 then establishes is negative: on this structure the vertex is not a covariance-aware hedge ratio at all but an artifact of an unnetted currency position, so the object the cross-hedging tradition would look for here does not survive inspection, and the case for setting the currency leg is made analytically instead (Section 7.5). The quanto literature, from Reiner’s drift-adjustment result onward, is a *valuation* literature: it prices the correlation coupling but leaves open the hedging problem that coupling implies, in which two correlated legs carry two notionals and one must be sized against the other. And the barrier-option hedging literature, including the continuity-correction result of Broadie, Glasserman, and Kou (1997), concentrates on the single-underlying discontinuity at the barrier, the delta’s explosion near the knock-out level, and not on cross-asset notional sizing. None of these strands examines a covariance-aware hedge ratio for a structure coupled through a shared barrier and a shared jump component. Deriving one in closed form, and measuring what an independent, per-asset treatment costs relative to it, is this paper’s contribution.

3 Asset Dynamics and P/Q Separation

3.1 Two-Asset Correlated Jump-Diffusion SDE

Let $S_1(t)$ denote the WTI crude price and $S_2(t)$ the USD/KRW exchange rate, both evolving under the physical measure $\mathbb{P}$. S_1 is modeled as a jump-diffusion process to capture the empirically fat-tailed, discontinuous behavior of energy prices; S_2 is modeled as a standard correlated geometric Brownian motion:

$$\frac{dS_1(t)}{S_1(t^-)} = (\mu_1^{\mathbb{P}} - \lambda\kappa) dt + \sigma_1 dW_1(t) + d\left(\sum_{j=1}^{N(t)} (e^{Y_j} - 1)\right) \quad (1)$$

$$\frac{dS_2(t)}{S_2(t)} = \mu_2^{\mathbb{P}} dt + \sigma_2 dW_2(t) \quad (2)$$

$$dW_1(t) \cdot dW_2(t) = \rho dt \quad (3)$$

$$\kappa = \mathbb{E}[e^Y - 1] = \exp(\theta_J + \tfrac{1}{2}\delta_J^2) - 1 \quad (4)$$

$N(t)$ is a Poisson counting process with intensity λ , independent of W_1, W_2 ; each jump multiplies the pre-jump price by e^{Y_j} , with the log-jump-size Y_j drawn i.i.d. from a normal distribution,

$$Y_j \sim \mathcal{N}(\theta_J, \delta_J^2). \quad (5)$$

For simulation, the SDE of Section 3.1 is discretized on a uniform grid $t_i = i\Delta t$, $i = 0, \dots, n$, $\Delta t = T/n$, using an Euler—Maruyama scheme with the compound Poisson jump superimposed once per step. On the risk-neutral measure $\mathbb{Q}$ constructed in Section 3.3 (drift $\mu_1^{\mathbb{P}} \rightarrow r_{US}$,

$\mu_2^{\mathbb{P}} \rightarrow r_{KRW} - r_{US}$), the one-step update is

$$\varepsilon_1 \sim \mathcal{N}(0, 1), \quad \varepsilon_2^\perp \sim \mathcal{N}(0, 1), \quad \varepsilon_2 = \rho \varepsilon_1 + \sqrt{1 - \rho^2} \varepsilon_2^\perp \quad (6)$$

$$N_i \sim \text{Poisson}(\lambda \Delta t), \quad J_i = \sum_{j=1}^{N_i} Y_j, \quad Y_j \stackrel{\text{iid}}{\sim} \mathcal{N}(\theta_J, \delta_J^2) \quad (7)$$

$$S_1(t_{i+1}) = S_1(t_i) \exp \left[\left(r_{US} - \lambda \kappa - \frac{1}{2} \sigma_1^2 \right) \Delta t + \sigma_1 \sqrt{\Delta t} \varepsilon_1 + J_i \right] \quad (8)$$

$$S_2(t_{i+1}) = S_2(t_i) \exp \left[\left(r_{KRW} - r_{US} - \frac{1}{2} \sigma_2^2 \right) \Delta t + \sigma_2 \sqrt{\Delta t} \varepsilon_2 \right] \quad (9)$$

The number of jumps N_i within a single step is itself simulated (not merely a 0/1 indicator), so that more than one jump landing in the same daily interval is representable, and the aggregate jump contribution J_i is the sum of that many independent draws of Y_j . The shared standard normal ε_1 drives both the diffusive part of S_1 and, through the $\rho \varepsilon_1$ term, the correlated part of S_2 's shock ε_2 ; this is the same Cholesky-style construction formalized in Section 3.3.

The introduction of the Poisson jump component converts the asset manifold from complete to incomplete. In a pure diffusion setting, the Black-Scholes replication argument holds exactly: a continuously-rebalanced portfolio of the underlying and a risk-free bond spans every contingent claim, because the only source of risk is a continuous Brownian increment that a continuously-adjusted delta position can offset instantaneously. A Poisson jump differs from a diffusive move in kind as well as in size: it is an instantaneous, discontinuous repricing that occurs at an unpredictable stopping time, and no finite adjustment made an instant before the jump can offset a discontinuity whose magnitude is drawn from a continuous distribution *after* the jump has already occurred. Because the space of possible jump outcomes cannot be spanned by a finite number of continuously-traded hedging instruments, the market admits infinitely many equivalent martingale measures and not the single one guaranteed under diffusion-only market completeness, and the choice among them is governed by the market's aggregate risk aversion toward jump risk specifically, a diversifiable-risk assumption this paper follows explicitly (Section 3.3) in choosing $\lambda, \theta_J, \delta_J$ to be measure-invariant.

The compensator term $-\lambda \kappa dt$ embedded in the drift is not an optional convention; it is required to keep the model's own stated drift parameter, $\mu_1^{\mathbb{P}}$, meaning what it is defined to mean. The compound Poisson jump term $\sum_{j=1}^{N(t)} (e^{Y_j} - 1)$ has, by construction, an instantaneous expected contribution of $\lambda \mathbb{E}[e^Y - 1] dt = \lambda \kappa dt$ to the process. If this expected jump contribution were left inside the total drift without being netted out, the realized expected growth rate of S_1 would exceed $\mu_1^{\mathbb{P}}$ by exactly $\lambda \kappa$, silently double-counting the jump component's mean inside a parameter that is supposed to represent the asset's total observed physical-measure drift. Subtracting $\lambda \kappa dt$ from the diffusive drift restores $\mu_1^{\mathbb{P}}$ as the asset's true expected growth rate under $\mathbb{P}$, and under the risk-neutral measure this same compensator structure (with $\mu_1^{\mathbb{P}}$ replaced by r_{US}) is the algebraic condition that keeps the discounted price process a local martingale, i.e. the condition without which no self-consistent pricing measure exists at all.

3.2 Quanto Double-Knock-Out Payoff Construction

Before turning to measure separation and calibration, it is worth writing the contract this paper prices and hedges out in full, since every subsequent formula is a derivative of this single object. The importer's exposure is to a monthly barrel requirement whose dollar cost, once converted to KRW, depends multiplicatively on both S_1 and S_2 ; the structure is built to offset that multiplicative joint exposure, at the smaller premium a barrier affords, by paying the same product $S_1 \cdot S_2$ only above a strike and only while WTI has stayed within a monitored corridor. Writing K for the strike, U and L for the upper and lower KO barriers ($U = 120$, $L = 50$ USD/bbl in the production configuration), and $\tau_{KO} = \inf\{t : S_1(t) \geq U \text{ or } S_1(t) \leq L\}$ for the first barrier-hitting time, the three payoff variants studied in this paper are:

$$V^{\text{Eur}}(T) = \text{barrels} \cdot \max(S_1(T) - K, 0) \cdot S_2(T) \cdot \mathbf{1}\{\tau_{KO} > T\} \quad (10)$$

$$V^{\text{Amer}}(\tau) = \sup_{\tau \leq T \wedge \tau_{KO}} \mathbb{E}^{\mathbb{Q}}[e^{-r_{US}\tau} \text{barrels} \cdot \max(S_1(\tau) - K, 0) \cdot S_2(\tau) \mid \mathcal{F}_0] \quad (11)$$

$$V^{\text{Asian}}(T) = \text{barrels} \cdot \max(\bar{S}_1(T) - K, 0) \cdot S_2(T) \cdot \mathbf{1}\{\tau_{KO} > T\}, \quad \bar{S}_1(T) = \frac{1}{m} \sum_{k=1}^m S_1(t_k) \quad (12)$$

where the supremum in the American payoff ranges over $\mathbb{Q}$ -measure stopping times τ that are themselves bounded by the first KO time τ_{KO} (once the barrier is hit the contract is dead and no exercise decision remains to be made), and $\bar{S}_1(T)$ in the Asian payoff is the arithmetic average of WTI over the m pre-specified averaging dates $t_1 < \dots < t_m \leq T$.

Each of these payoffs multiplies a WTI-leg quantity by the *floating* terminal FX rate $S_2(T)$ and not by a rate fixed at inception; this is the source of the "quanto" correlation coupling referenced throughout the paper. Because $S_1(T)$ and $S_2(T)$ are jointly, non-trivially correlated under the model of Section 3.1 (through the shared shock $\rho\varepsilon_1$ appearing in both legs' discretized increments), the risk-neutral expectation of the product does not factor into a product of expectations:

$$\mathbb{E}^{\mathbb{Q}}[\max(S_1(T) - K, 0) \cdot S_2(T)] \neq \mathbb{E}^{\mathbb{Q}}[\max(S_1(T) - K, 0)] \cdot \mathbb{E}^{\mathbb{Q}}[S_2(T)]. \quad (13)$$

The inequality in (13) is correct as stated, and it is tempting to read it as saying that ρ enters the price. It does not. The payoff converts at the *realized* terminal rate rather than at a rate fixed in advance, and that is precisely the case in which a change of numeraire removes the correlation entirely.

Proposition 1 (Factorization). *Let $N(t) = S_2(t)e^{r_{US}t}$ be the KRW value of the USD money-market account, a traded KRW asset, and let $\mathbb{Q}^{US}$ be the measure it induces. For any payoff of the form $X(T) \cdot S_2(T)$ with X measurable with respect to the S_1 path,*

$$V(0) = \mathbb{E}^{\mathbb{Q}^{KRW}}[e^{-r_{KRW}T} X(T) S_2(T)] = S_2(0) e^{-r_{US}T} \mathbb{E}^{\mathbb{Q}^{US}}[X(T)], \quad (14)$$

in which neither ρ nor σ_2 appears. The same holds for any optimal-stopping payoff of this form, since continuation and exercise values are both linear in S_2 .

The proof is the numeraire change itself: $V(0) = N(0) \mathbb{E}^{\mathbb{Q}^{US}}[X(T)S_2(T)/N(T)] = S_2(0)e^{-r_{US}T} \mathbb{E}^{\mathbb{Q}^{US}}[X(T)]$. Setting $X(T) = \max(S_1(T) - K, 0)\mathbf{1}_{\{\text{no barrier touch}\}}$ gives this paper’s European structure. The American value is a supremum over stopping times and is not of the form (14) covers; the argument extends to it because the numeraire ratio $S_2(t)e^{r_{US}t}/N(t)$ is identically one at every stopping time, so the same change of measure applies pathwise inside the supremum and the exercise region, being S_1 -measurable, is unchanged. Appendix B proves the extension. The correlation adjustment $-\rho\sigma_1\sigma_2$ that a KRW-numeraire treatment applies to the drift of S_1 is exactly offset by the $+\rho\sigma_1\sigma_2$ generated by the covariance between $X(T)$ and $S_2(T)$; the two cancel, which is what (14) records. Direct simulation confirms it, and confirms it with the barrier in place rather than only for the vanilla case: repricing the double-knock-out payoff at $\rho \in \{-0.5, 0, 0.0876, 0.5\}$ under the correctly-specified measure moves the value by at most 0.6%, non-monotonically in ρ and so within Monte Carlo error, against a factorized closed form agreeing to the same tolerance. The survival probability is likewise flat across ρ (0.741–0.743). This is what (14) predicts: the numeraire change shifts the drift of S_1 from $r_{US} - \rho\sigma_1\sigma_2$ under $\mathbb{Q}^{KRW}$ to r_{US} under $\mathbb{Q}^{US}$, so the first-passage law that governs the barrier is itself ρ -free.

The numeraire argument itself is standard; what it settles here is not. Practitioner usage prices this structure as a quanto and attributes a correlation coupling to it, and the Shapley split of Section 6.1 allocates premium between a WTI and an FX leg on that basis. Proposition 1 shows the coupling is absent from the price, which is a statement about a live pricing convention rather than about the mathematics. Three consequences follow for the rest of the paper. First, the label “quanto” is used here in its loose desk sense, for a two-asset structure whose payoff is denominated across currencies, and not in the technical sense of a fixed-conversion-rate contract carrying a correlation-dependent drift adjustment: this structure carries no such adjustment. A genuine quanto would convert at a rate fixed at inception, and only then would ρ survive into the price; in the cross-currency taxonomy the structure studied here is a *composite* (compo) option, and Proposition 1 is the textbook composite-option factorization (Musiela and Rutkowski, 2005), restated and verified because the desk convention this paper measures prices the structure as the quanto it is not. Second, Proposition 1 *is* the homogeneity result that Section 7.5 derives independently and uses to obtain $\delta_{FX} = V/S_2$; the FX-delta results of this paper are therefore consequences of the factorization rather than of any correlation coupling, and they are strengthened by it, since (14) makes the structure’s entire FX exposure its own carrying value by construction. Third, the factorization closes the pricing channel but not the question of how the two legs’ hedge costs co-move, which Section 7.4 takes up directly and finds to be dominated by a bookkeeping artifact rather than by the structural correlation.

All three benchmark engines draw their FX multiplication from the same jointly-simulated bank, so the FX leg is never a source of divergence between them (Section 6.1); only the barrier treatment is.

3.3 Orthogonal Girsanov Transform and Risk Premium Isolation

Write the correlated shocks in an orthogonal basis, $\epsilon_1 = z_1$, $\epsilon_2 = \rho z_1 + \sqrt{1 - \rho^2} z_2$, with market prices of risk $\theta_1 = (\mu_1^{\mathbb{P}} - r_{US})/\sigma_1$ and $\theta_2 = (\mu_2^{\mathbb{P}} - (r_{KRW} - r_{US}))/\sigma_2$. Shifting ϵ_2 by θ_2 directly

would price the WTI risk premium twice, since ϵ_2 already carries a ρ -weighted share of the z_1 shock that θ_1 shifts; the orthogonalized currency premium, acting purely on z_2 , is

$$\theta_{2,\text{indep}} = \frac{\theta_2 - \rho \theta_1}{\sqrt{1 - \rho^2}}, \quad (15)$$

and with the Girsanov density built from (θ_1 on z_1 , $\theta_{2,\text{indep}}$ on z_2) the $\mathbb{Q}$ -drifts reduce exactly to r_{US} and $r_{KRW} - r_{US}$ with no correlation leakage. Section 8 validates the construction twice: exactly, against closed-form drift moments; and inexactly, by likelihood-ratio reweighting of the path-dependent KO payoff, whose residual localizes numerical and not theoretical error.

4 Calibration of WTI Jump/Diffusion Inputs

A naive historical volatility estimator measures the *total* quadratic variation, diffusion plus jumps. Assigning it entirely to σ_1 and then layering Poisson jumps on top simulates strictly more variance than was ever observed, silently inflating both the premium and every downstream hedge cost. The calibration must therefore *split* the observed variance and not duplicate it.

4.1 Asymmetric Up/Down Jump Decomposition

The production calibration resolves this by classifying jump days with a robust k -sigma threshold and estimating an *up*-jump and a *down*-jump regime separately by moment-matching within each classified regime, since energy-price shocks are empirically asymmetric, with downside dislocations sharper than upside recoveries; the diffusive σ_1 is then re-estimated from the surviving non-jump days, so the observed quadratic variation is split between the two components rather than duplicated. Appendix C states the estimator in full, including what it is not.

Because every downstream engine in this paper (Sections 3.1–5) simulates a single symmetric jump distribution and not two asymmetric regimes, the fitted $(\lambda_{up}, \theta_{J,up}, \delta_{J,up})$ and $(\lambda_{dn}, \theta_{J,dn}, \delta_{J,dn})$ pairs are moment-matched to a single equivalent Poisson-normal jump $(\lambda, \theta_J, \delta_J)$ by matching total jump intensity, the aggregate first moment, and the aggregate second moment of the jump-size distribution:

$$\lambda = \lambda_{up} + \lambda_{dn} \quad (16)$$

$$\theta_J = \frac{\lambda_{up} \theta_{J,up} + \lambda_{dn} \theta_{J,dn}}{\lambda} \quad (17)$$

$$\delta_J^2 = \frac{\lambda_{up}(\theta_{J,up}^2 + \delta_{J,up}^2) + \lambda_{dn}(\theta_{J,dn}^2 + \delta_{J,dn}^2)}{\lambda} - \theta_J^2 \quad (18)$$

The three lines match, in order, the total arrival rate, the intensity-weighted mean (preserving the compensator $\lambda\kappa$ of Section 3.1), and the pooled second moment, an exact two-to-one variance decomposition.

Table 1 reports the fitted regimes directly, and not only the symmetrized pair the downstream engines consume. Down-jumps arrive nearly twice as often as up-jumps ($\lambda_{dn} = 4.462$ vs. $\lambda_{up} = 2.328$ per year), are roughly 9% larger in magnitude ($|\theta_{J,dn}| = 8.75\%$ vs. $\theta_{J,up} = 8.04\%$), and are 66% more volatile ($\delta_{J,dn} = 2.78\%$ vs. $\delta_{J,up} = 1.68\%$). The asymmetry is a measured

property of the return history ($n_{up} = 12$, $n_{dn} = 23$ classified jump days).

A note on what this estimator is. Jump days are identified by a k -sigma threshold rule and the intensity is their annualised count: $35 \times 252/1300 = 6.7846$ per year reproduces the figure the engines use to seven digits, and the two regime intensities are $12 \times 252/1300$ and $23 \times 252/1300$. It is a threshold classifier followed by moment-matching within each regime, not the likelihood-maximising mixture that “EM” would imply, and the symmetrized triple $(\lambda, \theta_J, \delta_J) = (6.7846, -0.0299, 0.08443)$ is what every engine in this paper consumes. Re-deriving the symmetrization from the rounded regime values displayed above returns $\delta_J = 0.0834$ rather than 0.08443, a 1.2% difference that is an artifact of the rounding rather than a second estimate. The estimation sample is the 1,300 paired returns of the price history.

Regime	λ (jumps/yr)	θ_J	δ_J	n days
Up-jump ($r > 0$)	2.328	+8.04%	1.68%	12
Down-jump ($r < 0$)	4.462	−8.75%	2.78%	23
Symmetrized (as used by the engines)	6.7846	−2.99%	8.443%	35

Table 1: Fitted up/down jump regimes and their moment-matched symmetrization, from the 1,299-day WTI daily log-return history ($k=3$ robust threshold).

The resulting decomposition: total historical WTI volatility $\sigma_1 = 0.3946$ splits into a diffusive $\sigma_1 = 0.3242$ and a symmetrized jump component $(\lambda, \theta_J, \delta_J) = (6.7846, -0.0299, 0.08443)$. The negative mean jump size is the asymmetric fit’s quantitative trace surviving symmetrization: the larger, more frequent down-jump regime pulls θ_J negative under intensity weighting. The FX leg calibrates to $\sigma_2 = 0.0926$ with WTI—FX correlation $\rho = 0.0876$, the quantity the orthogonal Girsanov construction of Section 3.3 isolates. Whether the up/down asymmetry itself matters for barrier risk is testable: simulating the genuine two-regime process against the symmetrized draw on matched seeds moves barrier-touch probabilities by under 0.1 percentage points even from starting points near the barrier, because the 32.4% diffusive volatility dominates touch dynamics over sub-annual horizons, so the symmetrization is quantitatively adequate for this structure and not merely tractable.

5 Numerical Model Formulation

5.1 Path Simulation and the Longstaff—Schwartz Backward-Induction Algorithm

Pricing and hedging every structure in this paper reduces, algorithmically, to a single backward-induction procedure applied to a bank of N jointly-simulated (S_1, S_2) paths built from the discretization of Section 3.1. Writing $\hat{V}_p(t_i)$ for the estimated value of the contract on path p at step i , the procedure is:

1. **Forward simulation.** Simulate all N paths forward from t_0 to $t_n = T$ using the one-step update of Section 3.1, recording $S_1(t_i, p)$, $S_2(t_i, p)$ at every step, and separately recording the first barrier-hitting step $i_{KO}(p)$ (identified via the Brownian-bridge test of Section 5.4, applied between each pair of consecutive recorded steps).

2. **Terminal initialization.** At $i = n$, set $\hat{V}_p(t_n) = \max(S_1(t_n, p) - K, 0) \cdot S_2(t_n, p)$ for the European and American payoffs (Section 3.2), or the corresponding running-average intrinsic value $\max(\bar{S}_1(T, p) - K, 0) \cdot S_2(t_n, p)$ for the Asian payoff, on every path not already knocked out by $i_{KO}(p) \leq n$; knocked-out paths carry a value of zero from their KO step onward.
3. **Backward loop.** For $i = n - 1, n - 2, \dots, 1$:
 - (a) Identify the in-the-money (ITM) path subset $\mathcal{I}_i = \{p : S_1(t_i, p) > K \text{ and } i < i_{KO}(p)\}$.
 - (b) On $\mathcal{I}_i$ only, regress the one-step-discounted continuation value $e^{-r_{US}\Delta t}\hat{V}_p(t_{i+1})$ against the 5-term polynomial basis of Section 5.2 evaluated at (v_1, v_2) at t_i , by ordinary least squares, to obtain the fitted coefficients $\beta_0(t_i), \dots, \beta_5(t_i)$.
 - (c) For American paths only: on $\mathcal{I}_i$, compare the fitted continuation value $\tilde{C}(S_1(t_i, p), S_2(t_i, p))$ against the immediate exercise value $\max(S_1(t_i, p) - K, 0) \cdot S_2(t_i, p)$; where exercise value exceeds continuation value, overwrite $\hat{V}_p(t_i)$ with the exercise value and mark path p as exercised at t_i (removing it from all subsequent backward steps).
 - (d) On every path not exercised at this step, set $\hat{V}_p(t_i) = e^{-r_{US}\Delta t}\hat{V}_p(t_{i+1})$ (out-of-the-money and previously-alive paths simply carry the discounted future value backward unchanged; the regression is used only to make the exercise decision, never to replace the realized future cash flow, which is the defining feature of the Longstaff—Schwartz estimator relative to a naive plug-in of the fitted surface).
4. **Price and Greeks.** The step-0 price is $\hat{V}(t_0) = \frac{1}{N} \sum_{p=1}^N \hat{V}_p(t_0)$ (the cross-sectional average of the backward-propagated cash flows), and the fitted coefficient set $\{\beta_0(t_i), \dots, \beta_5(t_i)\}_{i=1}^n$ retained from step 3(b) at every time step is what Section 5.3 differentiates analytically to obtain the hedging delta at each rebalancing date, so no separate pricing pass is required to extract the Greek once the backward loop above has been run once.

This is the standard Longstaff—Schwartz (2001) least-squares Monte Carlo estimator, with two structure-specific modifications relative to its textbook presentation: the ITM path subset in step 3(a) additionally excludes any path already knocked out ($i < i_{KO}(p)$), so the regression is never fitted using post-barrier paths whose future cash flow is trivially zero; and step 3(c) (the exercise comparison) is applied only for the American engine, so that the identical steps 1, 2, 3(a), 3(b), 3(d), and 4, unmodified, also constitute the full pricing and delta-extraction procedure for the barrier-only European and Asian engines, with early exercise simply never triggering.

5.2 Corrected State-Variable Normalization and the 5-Term Polynomial Basis

The cross-sectional LSMC regression at each time step fits the discounted continuation value against a 5-term polynomial in two normalized state variables (five regressor terms plus a

constant, six coefficients $\beta_0, \dots, \beta_5$ in total, the count referenced throughout this paper as “5-term,” and, where every coefficient is tallied explicitly as in Table 16, as “6-term”). Writing K for the option strike (set at-the-money-forward, $K = S_1(0)$, in the production configuration) and $S_2(0)$ for the inception FX spot, the normalized variables are

$$v_1 = \frac{S_1}{K} \tag{19}$$

$$v_2 = \frac{S_2}{S_2(0)} \tag{20}$$

so that $v_1, v_2 \approx 1$ near inception and both regressors move in direct, not inverse, proportion to the underlying spot. (An inverted definition $v_1 = K/S_1$ would explode as $S_1 \rightarrow 0$, a numerically valid state in a distressed commodity path, and would destabilize the regression’s matrix conditioning; the production code avoids this by construction.) The continuation value surface is then

$$\tilde{C}(S_1, S_2) = \beta_0 + \beta_1 v_1 + \beta_2 v_2 + \beta_3 v_1^2 + \beta_4 v_2^2 + \beta_5 v_1 v_2 \tag{21}$$

fitted by ordinary least squares, in-the-money paths only, independently at each of the 217 discrete time steps spanning the $T = 0.833$ -year (approximately ten-month) horizon. This is step 3(b) of the backward-induction algorithm of Section 5.1, and the six coefficients solved at every step form the full pricing surface that algorithm accumulates. Section 8.3.2 (Table 16) bounds how much this particular basis choice matters by pricing the same structure under a strictly larger cubic basis, a genuinely non-polynomial exponentially-weighted Laguerre-function basis, and a payoff-kink-augmented basis, bounding the basis effect at one percent, and showing that kink-aware terms are no-ops under ITM-only fitting, since the hinge is linear on the fitted region.

5.3 The Closed-Form LSMC Regression Delta

The hedging gradient is obtained analytically by differentiating the fitted polynomial surface with respect to S_1 and rescaling into FX-adjusted notional terms, using $\partial v_1 / \partial S_1 = 1/K$:

$$\delta_{WTI}^{\text{Amer}} = \text{clip}_{[0,1]} \left(\frac{1}{S_2} \cdot \frac{1}{K} (\beta_1 + 2\beta_3 v_1 + \beta_5 v_2) \right) \tag{22}$$

$$\delta_{FX} = c \cdot \delta_{WTI}, \quad c = 1.0 \tag{23}$$

This is the exact closed-form derivative of the fitted regression surface; no finite-difference re-pricing is required, so the delta is available at zero marginal simulation cost once $\beta_0, \dots, \beta_5$ are known at a given step. Each term of the polynomial maps to an interpretable hedging quantity: β_1 is the surface’s static linear delta; $2\beta_3 v_1$ is a moneyness-dependent acceleration term acting as an implicit local gamma; $\beta_5 v_2$ injects the cross-asset correlation directly into the WTI hedge ratio, so that a shift in the FX leg alone can move the required WTI hedge notional. The $\text{clip}_{[0,1]}$ bound is an operational constraint on the regression’s own fitting noise, which is unbounded in principle and would otherwise occasionally instruct the desk to hold an

over-leveraged position. An up-and-out call has a genuinely *negative* delta as spot approaches the upper barrier, because a further rise makes extinction more likely, and one might expect the lower clip to be removing that. Section 7.2 measures it and finds the opposite: the raw gradient never turns negative anywhere, so the clip binds only above, on 1.42% of nodes, and removing it entirely leaves the hedge-cost mean unchanged and moves the standard deviation by 0.04%. The sign reversal is absent from the estimator by construction of the basis, not removed by the clip. Section 7.1 documents empirically how large the gap between this closed-form regression delta and the numerical finite-difference delta actually is, and where in the option's life that gap is largest.

5.4 Log-Space Brownian Bridge Barrier Correction: Upper and Lower Barriers

A discretely-recorded path can cross a barrier between two observations and revert, leaving no trace on the grid, a systematic *under*-detection that would overprice the structure. This is the discrete-monitoring bias formalized by Broadie, Glasserman, and Kou (1997); the correction implemented here is their bridge-probability treatment applied directly on each discretization interval, and not their alternative barrier-shift approximation, since the per-step conditional touch probability is available in closed form once the interval's endpoints are known. The correction applies, on each step with both recorded endpoints interior to $[L, U]$, the exact Brownian-bridge touch probability in log-space for each barrier:

$$p_{up} = \exp\left(\frac{-2 \ln(U/S_1^{\text{prev}}) \ln(U/S_1)}{\sigma_1^2 \Delta t}\right), \quad p_{dn} = \exp\left(\frac{-2 \ln(S_1^{\text{prev}}/L) \ln(S_1/L)}{\sigma_1^2 \Delta t}\right), \quad (24)$$

each compared against an independent uniform draw once per step; endpoints on or beyond a barrier are direct discrete touches. A positive bridge test updates only the KO flag and index $i_{KO}(p)$, never the recorded values.

Both p_{up} and p_{dn} are mathematically exact under the strict assumption that the path between the two endpoints is continuous. Under the model of Section 3.1, that assumption is only approximately true: a genuine Poisson jump can teleport the price across a barrier discontinuously, a scenario the continuous bridge formula was never derived to capture, since it has no mechanism for a jump that occurs *between* the two conditioning endpoints and is not itself one of the two recorded values. Formally, the true step-conditional touch probability decomposes as

$$\mathbb{P}(\tau_{KO} \in (t_i, t_{i+1}] \mid S_1(t_i), S_1(t_{i+1})) = p_{up} + \mathcal{E}_{\text{jump}}(\lambda, \theta_J, \delta_J; \Delta t), \quad (25)$$

where $\mathcal{E}_{\text{jump}} \geq 0$ collects the paths the bridge test cannot see: a jump lands strictly inside (t_i, t_{i+1}) , crosses U (or L), and reverts in log-price to the interior of $[L, U]$ by t_{i+1} , indistinguishable from the two recorded endpoints alone from a jump-free path that stayed inside the barrier throughout. Such a path requires both a jump landing in an interval of length Δt (probability $O(\lambda \Delta t)$) and that jump crossing a barrier several diffusive standard deviations from the endpoint, so $\mathcal{E}_{\text{jump}} = O(\Delta t)$ and $\mathcal{E}_{\text{jump}} \rightarrow 0$ as $\Delta t \rightarrow 0$, vanishing at the same order as the

Euler—Maruyama discretization error the bridge correction was already built to control. Given the daily granularity of the production grid (217 steps over 0.833 years, i.e. roughly one step per trading day), this residual is small in expectation, since a typical single jump of magnitude $\theta_J \pm \delta_J \approx -3.0\% \pm 8.4\%$ against barriers set at $+52\%/-37\%$ from spot is very unlikely to itself be the difference between touching and not touching the barrier within a single day, and (25) makes explicit that it is nonzero.

6 Empirical Results

6.1 Baseline Pricing and the Knock-Out Rate

At the production baseline ($S_1(0) = 78.94$ USD/bbl, $S_2(0) = 1,540.64$ KRW/USD, $r_{US} = 4.0\%$, $r_{KRW} = 3.5\%$, KO barriers at 50/120 USD/bbl), the LSMC-priced base premium is KRW 17,132.47 per quanto unit, scaling to a total structure premium of KRW 34,264,941,589 across the full 2,000-contract (2,000,000 barrel) position. A Shapley-style attribution of this premium across the two legs assigns KRW 15,093.75 (88.1%) to the WTI leg and KRW 2,038.72 (11.9%) to the FX leg, consistent with the WTI leg carrying the dominant share of both notional and volatility in this structure.

All hedge simulation results reported below are computed on $n = 10,000$ independent common-random-number paths, rebalanced daily over 217 steps.

The KO rate is not a single invariant number, and reporting it as one number obscures a genuine structural feature of the American engine. On the shared path bank, the two engines whose stopping rule tests the barrier alone (European with the Black-76 proxy delta, and Asian with the Turnbull—Wakeman proxy delta) report an identical KO rate of 0.4369, confirming that both engines are evaluated on the same underlying barrier-touch process. The American engine reports a strictly smaller KO rate of 0.2309, alongside an early-exercise rate of 0.4474. This is not evidence of a different barrier process for American; it is the direct consequence of early exercise being a competing first-stopping-time event: on any path where the American holder’s optimal-stopping rule triggers exercise before the barrier is touched, that path is tallied as “exercised,” not “knocked out,” even though the identical underlying path, had it been held without an exercise option, would eventually register a barrier touch and would be counted in the 0.4369 figure. The three rates partition the American path population into exercise (44.74%), KO (23.09%), and alive-to-maturity (32.17%), and the correct empirical statement is that the raw barrier-touch frequency on this path bank is 0.4369, with American’s early-exercise feature pre-empting roughly half of what would otherwise have been KO outcomes.

6.2 Hedge Cost: American LSMC vs. Closed-Form Proxies

The primary comparison metric used throughout is *hedge cost*, defined per path as $HC = \Pi_{\text{option}} - \Pi_{\text{delta}}$, the realized option profit net of total delta-hedge profit. It is distinct from *total P&L*, which is reported in Tables 8 and 11 and additionally carries the premium outlay and the physical-leg settlement, so the two are not directly comparable in level; hedge cost which by construction isolates the performance of the delta strategy itself and does not conflate delta quality with the underlying payoff-structure differences between an American, European, and

KO rate	Path bank / measure	Definition	Section
0.4369	shared bank, $\mathbb{Q}$	barrier touch, daily grid	6.1
0.2309	shared bank, $\mathbb{Q}$	barrier touch net of early exercise (American)	6.1
0.4551 / 0.2249	FX-sweep bank, $\mathbb{Q}$	exercise / KO net of exercise	7.3
0.4391 / 0.4377	rigor bank, $\mathbb{Q}$	barrier touch, exact / production scheme	8.3
0.4512 / 0.4494	rigor bank, $\mathbb{P}$	barrier touch, exact / production scheme	8.3
0.171–0.174	k -sweep banks, $\mathbb{Q}$	KO net of exercise, re-fitted and re-struck per k	7.7

Table 2: Reference table of every knock-out rate reported in this paper, with the path bank and definition each figure belongs to. Rates from different banks or definitions are not comparable with one another; each section’s inference uses only rates from its own row.

Asian claim. Table 3 reports the full-population ($n = 10,000$) mean and standard deviation of hedge cost under each of the three delta-estimation methods.

Table 3: Hedge cost distribution, full population ($n = 10,000$), KRW		
Engine (delta method)	Mean hedge cost	Std. dev. hedge cost
American (LSMC regression)	4,242,549,693	54,406,045,559
European (Black-76 proxy)	66,914,895,880	117,398,625,340
Asian (Turnbull—Wakeman proxy)	66,423,885,856	110,073,446,997




Figure 2: Mean hedge cost and one standard deviation, full population, by delta-estimation method.

Two scale references make the levels legible before any comparison is drawn: the notional being hedged is 2,000,000 barrels, roughly KRW 240bn of procurement value at spot, and the structure’s premium is KRW 34.3bn, so proxy-arm mean hedge costs near KRW 67bn are of the same order as the position economics rather than small residuals; Section 6.3 decomposes how much of that level is delta quality (little) and how much is payoff, premium and stopping-time mismatch between the arms (most). The LSMC regression delta’s mean hedge cost (KRW 4.24 billion) is smaller than either closed-form proxy’s by roughly a factor of fifteen, and its standard deviation is smaller by a factor of two. Because the full-population comparison mixes paths with genuinely different payoff structures (KO’d paths, early-exercised paths, and paths

alive to maturity all pool together, and American, European, and Asian pay off differently even conditional on an identical path), a second, cleaner test isolates the $n = 3,217$ paths (32.2% of the population) that are simultaneously non-KO and non-early-exercised, the subset on which American and European pay off *identically* ($\max(S_1(T) - K, 0) \cdot S_2(T)$ on a shared path), so that any remaining hedge-cost difference is attributable purely to the delta-estimation method and nothing else.

Table 4: Hedge cost, clean subset (non-KO, non-exercise, $n = 3,217$), KRW

Engine	Mean hedge cost	Std. dev. hedge cost
American (LSMC regression)	26,928,215,657	36,765,911,185
European (Black-76 proxy)	91,526,694,827	91,558,547,428




Figure 3: Hedge cost, clean (non-KO, non-exercise) subset: pure delta-method comparison.

On the clean subset, though see Section 6.3 for why this control is insufficient,, the LSMC regression delta’s mean hedge cost is KRW 64.6 billion lower and its standard deviation is roughly $2.5\times$ smaller than the Black-76 proxy delta’s, on paths where both models are pricing and differentiating literally the same closed-form payoff. This does not isolate the delta rule. Conditioning on the American engine’s own exercise decision is selection on an endogenous, delta-correlated event, and a proper control that fixes contract, premium and stopping time leaves a factor of 1.12 rather than 15.8. What remains true of the clean subset is only that one delta is computed on the same simulated paths that determine the P&L, and the other from a model that has no barrier term at all. As a final decomposition, the raw option-payoff bias between engines on identical paths (independent of hedge cost) is $\text{Mean}(V_{Am}) - \text{Mean}(V_{Eu}) = -\text{KRW } 23.86$ billion and $\text{Mean}(V_{Am}) - \text{Mean}(V_{As}) = -\text{KRW } 28.57$ billion, confirming that early exercise materially lowers American’s realized option payoff relative to the European and Asian proxies on the same underlying paths, separately from and in addition to its hedge-cost advantage.

6.3 Decomposing the Gap: The Contribution of the Delta Rule

Table 3 compares an American LSMC ledger against European and Asian proxy ledgers, and the three arms differ in more than the delta rule. They carry different payoffs, different premiums

and different stopping times, and in the shipped implementation the proxy arms hedge only the WTI leg while the LSMC arm hedges both. Section 6 already reports one component of this directly, $\text{Mean}(V_{Am}) - \text{Mean}(V_{Eu}) = -\text{KRW } 23.86\text{bn}$, which enters the mean hedge cost one for one. The comparison must therefore be decomposed before the delta rule can be credited with any of it.

Holding the contract, the premium, the path bank and the stopping rule fixed, and varying *only* the delta rule, gives a much smaller effect. On 100,000 common paths with both arms held to maturity:

delta rule (common European ledger)	mean HC	sd HC
fitted surface	-22.86bn	51.29bn
Black-76 proxy	-23.02bn	57.23bn

The means are within 0.7% of each other and the standard deviations differ by a factor of 1.12, not the $15.8\times$ and $2.16\times$ of Table 3. That 1.12 is small but it is not noise: repeated over five independent surface-and-hedge seed pairs the ratio is 1.1156 with a standard deviation of 0.0040 across seeds, so it stands at 65 standard errors from unity. The residual is attributable to the contract: terminating the ledger at the LSMC exercise time on roughly 45% of paths shortens the hedging horizon on exactly those paths, and hedging error accumulates with the length of the hedge.

One further control is necessary before the surviving 12% can be attributed to anything. Section 7.2 shows the surface delta is close to constant over the fitted domain, around 0.70. If a flat hedge ratio at that level reproduces the advantage, then the gain is a property of the ratio's *level* and not of any state dependence, barrier-related or otherwise. Run on the same bank:

hedge rule (common European ledger)	mean HC	sd HC
fitted surface, state-dependent	-22.86bn	51.29bn
Black-76, state-dependent	-23.02bn	57.23bn
constant $\delta = 0.70$, no state dependence	-24.00bn	51.13bn
constant $\delta = 0.70$ plus the surface FX leg	-22.87bn	51.77bn

The constant-delta hedge matches the fitted surface and slightly beats it: the dispersion ratio against Black-76 is 1.119 for the constant and 1.116 for the surface. The entire advantage is reproduced by a number, with no fitting, no path bank and no barrier information of any kind.

The constant is not an optimum and must not be presented as one. Dispersion falls monotonically as the ratio falls across the whole tested range, from KRW 69.6bn at $\delta = 1.00$ through 57.0 at 0.80, 51.0 at 0.70, 49.8 at 0.68, 45.1 at 0.60 to 39.5 at 0.50, with no interior minimum. The value 0.70 was chosen because it is the level at which a constant reproduces the fitted surface, not because it optimises anything, and a constant of 0.50 beats Black-76 by thirty percent rather than twelve.

This is the paper's most useful result, and it is prescriptive rather than merely negative. On this structure and this calibration, a barrier-aware LSMC regression delta does not beat a barrier-blind closed-form delta because it is barrier-aware. It beats it because Black-76's delta rises toward one as the option goes into the money while a knock-out structure's does not, so

any rule that keeps the ratio below Black-76’s captures most of the gain. The five-term surface is one such rule; a constant at the surface’s own level is another, is cheaper, and is slightly better. Claims that a fitted exercise surface delivers barrier-aware hedging should be tested against a constant-delta control before being accepted.

Even the 12% on this like-for-like ledger is not the end of the decomposition. This ledger runs both arms to maturity, and Section 6.4 shows that holding the contract fixed *that* way charges a European payoff an American premium; stopping the ledger where the price says the contract stops reverses the sign, and the barrier-blind delta becomes the better hedge. The 12% should therefore be read as the largest advantage the surface retains under any consistent control, not as a standing result: the much larger raw gap in Table 3 is dominated by payoff, premium and stopping-time differences between the three engines rather than by delta quality, and what is left once those are removed does not survive the exercise-consistency correction either. The trimodality of Section 6.5 is a property of the proxy ledgers as configured and inherits the same caveat.

6.4 The comparison under a consistent ledger

Section 6.3 holds the contract fixed by running both arms to maturity. That is one of two ways to make the comparison consistent, and it is the wrong one: the premium charged in every ledger is $\text{fit}[\text{price}]$, an American value produced by a backward induction that applies the exercise rule, so a ledger that runs to maturity charges an American premium against a European payoff. The consistent alternative stops the ledger at the fitted exercise time and books intrinsic value there.

Under that correction the central comparison of this paper reverses.

ledger	surface δ	Black-76 δ	winner
as shipped (no exercise, gross FX)	51.50bn	57.42bn	surface, by 1.12×
exercise-consistent	23.81bn	12.58bn	Black-76, by 1.89×
exercise-consistent, FX netted	20.53bn	12.58bn	Black-76, by 1.63×

Hedge-cost standard deviation, 60,000 paths on a surface fitted at 200,000. The regression delta beats the closed-form proxy only in the configuration that charges a European ledger an American premium. Once the ledger stops where the price says the contract stops, the barrier-blind Black-76 delta is the better hedge on this structure by a factor between 1.6 and 1.9, and netting the oil leg’s currency exposure widens the gap rather than closing it.

This completes the decomposition the Introduction promised. What survives of the raw comparison is the diagnosis in Section 7.2: the fitted surface is close to a constant over its fitted domain and does not reproduce the sign reversal a barrier delta carries, so there was never a mechanism by which it should have beaten a well-specified closed form. The configuration in which it appears to win is the one that mixes two contracts.

6.5 Empirical Total-P&L Distribution vs. a Fitted Normal

Tables 3—4 report only the first two moments of hedge cost. To characterize the full shape of the realized total-P&L distribution, and to test directly whether it is even approximately normal

and not assuming it, Figure 4 plots the empirical histogram of total P&L across all 10,000 simulated paths for each engine, overlaid with a normal density fitted to the same empirical mean and standard deviation. Table 5 reports the corresponding skewness and excess kurtosis, computed directly from the per-path ledger (the production model itself reports these moments only for the American engine; the European and Asian figures are computed here for the first time from the underlying 10,000-path data).

Table 5: Total-P&L distribution moments, full population ($n = 10,000$)

Engine	Mean (bn KRW)	Std. dev. (bn KRW)	Skewness	Excess kurtosis
American (LSMC regression)	−38.74	26.52	0.13	1.33
European (Black-76 proxy)	−77.55	132.60	−0.56	−0.89
Asian (Turnbull—Wakeman proxy)	−72.36	119.18	−0.77	−0.91

Empirical total-P&L distribution vs. fitted normal density (n=10,000 paths per engine)




Figure 4: Empirical total-P&L distribution (gray histogram) vs. a normal density fitted to the same mean and standard deviation (black dashed), by engine.

The contrast is stark. American’s total-P&L distribution is unimodal and only mildly non-normal (skewness 0.13, excess kurtosis 1.33); both proxy engines are *trimodal* at a default kernel bandwidth, with a severe-loss cluster near −KRW 280—300 billion, a moderate-loss cluster, a smaller gain cluster. Their failure of normality is not tail thickness (both are mildly platykurtic, −0.89 and −0.91) but multimodality: three sub-populations sorted by which of the barrier, the FX co-movement, and the (absent) barrier-aware delta protection each path realizes. A

proxy delta does more than add noise: it produces a categorically different, multi-regime P&L distribution that its own mean and standard deviation cannot summarize. The modality claim is bandwidth-sensitive and is reported as such: a Gaussian kernel density on the proxy ledger at Scott’s default bandwidth resolves three local maxima, near KRW -252bn , -130bn and $+2\text{bn}$, but widening the bandwidth by a factor of two collapses these to two and by a factor of three to one. The distribution is therefore broad and left-skewed (skew -1.39 , excess kurtosis $+0.35$) with structure at the default resolution, and the paper does not claim a formally tested multimodality; no dip test is reported.

6.6 Alive-and-In-the-Money Path Density

The regression’s step-wise reliability depends on the alive-and-ITM path count. Figure 5 reports that fraction by elapsed time across six maturities: from a life-mean of 45.7% at 0.5 years down to 18.9% at 3.0 years, with the 3.0-year structure’s terminal fraction at just 3.0%, the mechanical reason regression reliability degrades with maturity (Section 7.1).




Figure 5: Alive-and-ITM path probability by elapsed time fraction, across six tested maturities.

7 Sensitivity Studies

7.1 Finite-Difference vs. Regression Delta

Table 6 and Figure 6 compare the closed-form LSMC regression delta of Section 5.3 against an independent finite-difference (bump-and-reprice) delta computed by re-running the full LSMC pricer at $S_1(0) \pm \varepsilon$, at three points across the structure’s life.

The re-measured gap is modest at inception and widens with elapsed time: 7.8% at $t/T = 0$, 28.3% at mid-life and 72.4% at $t/T = 0.9$. Two features of the measurement matter. First, the bump must hold the contract strike fixed. Bumping the spot while letting K follow it measures the sensitivity of a permanently at-the-money contract to a joint translation of spot and strike, which is a different object and, on this structure, roughly an order of magnitude smaller. Table 6 holds $K = 78.94$ throughout. Second, with the strike fixed the price is monotone increasing in

Table 6: Finite-difference vs. regression delta, WTI leg. Both columns re-measured on the exact engine at 100,000 paths per replication over five independent seeds; standard deviations across seeds in parentheses. The finite difference is a central bump-and-reprice at $\varepsilon = 5\%$ with the contract strike *held fixed* at $K = 78.94$ while the spot is bumped, which is the sensitivity a hedging desk needs.

t/T	FD delta	Regression delta	Abs. diff.	% of FD
0.00	0.5342 (0.0055)	0.5759 (0.0772)	0.0417	7.8%
0.50	0.5457 (0.0066)	0.6999 (0.0200)	0.1542	28.3%
0.90	0.5355 (0.0010)	0.9232 (0.0361)	0.3877	72.4%




Figure 6: Finite-difference delta vs. LSMC regression delta, by elapsed time fraction.

spot over $S_1(0) \in [71, 103]$, with an average slope of 0.58; the barrier at $U = 120$ does not turn the value over inside that range at a ten-month horizon.

The direction of the remaining gap is the informative part. The regression delta is close to the finite difference early, when the option is at the money and the barrier is far, and drifts above it as the option ages: by $t/T = 0.9$ it reads 0.92 against a measured 0.54. This is the opposite of the profile a converging estimator would show, and it is consistent with what Section 7.2 documents below, namely that the fitted surface has very little state dependence at all. The finite-difference side is the tightly determined one throughout, with a seed standard deviation of 0.006 or less; the regression side carries a seed dispersion of 0.077 at inception, which Section 7.2 traces to a rank-deficient first-step design matrix.

The consequence for the rest of the paper is bounded. The hedge-cost comparisons of Section 6.2 compare two hedging *rules* applied to identical paths and do not require either delta to be an accurate price sensitivity. Any use of the regression gradient as $\partial V / \partial S_1$, on the other hand, carries an error that grows from under ten percent at inception to more than seventy percent near expiry, and a desk sizing from it late in the option's life would over-hedge accordingly.

7.2 State Dependence of the Fitted Surface

The level comparison above says the surface is close to correct early and drifts high late. A sharper question is whether it varies with the state at all. Table 7 compares the surface delta with the barrier-blind Black-76 delta by moneyness bucket at mid-life, on a common 100,000-path bank restricted to in-the-money survivors.

WTI bucket	nodes	surface δ	Black-76 δ
[79, 85)	11,102	0.7087	0.6003
[92, 100)	9,005	0.6958	0.8318
[115, 120)	522	0.6761	0.9592

Table 7: Regression-surface delta against the Black-76 delta by moneyness at $t/T = 0.5$. The surface delta spans 0.033 across the entire in-the-money domain; the Black-76 delta spans 0.36.

The result is negative and it should be reported as such. Across the whole in-the-money domain the surface delta moves by 0.033, from 0.709 just above the strike to 0.676 within five dollars of the barrier, while the Black-76 delta moves by 0.36 over the same range. The surface is a constant plus fitting noise. Its apparent “damping” near the barrier, 0.676 against Black-76’s 0.959, is not damping: just above the strike the same surface reads 0.709 against Black-76’s 0.600, high by the same order and in the wrong direction. A genuine up-and-out delta rises with moneyness and then collapses toward and through zero as the barrier approaches; this one does neither.

Two further diagnostics complete the picture. Over 17,342,543 hedged nodes the raw delta never turns negative, with a minimum of +0.357 and +0.582 within ten percent of the upper barrier, so the clip_[0,1] of Section 5.3 never binds below; the upper clip binds on 1.42% of nodes, and removing the clip entirely leaves the hedge-cost mean unchanged and moves the standard deviation from KRW 51.25bn to 51.27bn. And at the first step the design matrix is badly conditioned, $\text{cond}(X'X) \approx 1.8 \times 10^{10}$ against the solver’s $\text{rcond} = 10^{-10}$, because v_1 and v_2 carry one day of cross-sectional dispersion; the fitted coefficients there are an order of magnitude larger than from step 20 onward and nearly cancel, which is the source of the inception seed dispersion and of the sign instability in $\partial V/\partial S_2$ discussed in Section 10.

The summary is therefore specific. The five-term surface is not a barrier-aware delta estimator in the sense the term usually implies: over the fitted domain it is close to a constant, it does not reproduce the barrier’s characteristic sign reversal, and it is poorly conditioned at inception. That is a substantive finding about a widely used construction, not a defect peculiar to this implementation, and it is measurable only because the structure admits an independent price sensitivity to test against. What Section 6.2 measures is the performance of the *hedging rule* the surface induces, which is a different and still useful question.

7.3 Hedge-Cost Sensitivity to the FX Coupling Multiplier

The one-parameter coupling $\delta_{FX} = c \cdot \delta_{WTI}$, evaluated at the natural reference point $c = 1.0$, is tested directly by sweeping $c \in \{0.5, 0.75, 1.0, 1.25, 1.5\}$ and holding the WTI delta strategy fixed. Table 8 and Figure 7 report the results; note that the KO rate (0.2249) and early-exercise

rate (0.4551) are, as expected, identical across every value of c , since c only rescales the FX leg and has no influence on the WTI-side stopping decisions, so any change in cost or variance across the sweep is attributable purely to the FX-leg coupling, not to a change in the underlying barrier or exercise behavior.

Table 8: FX hedge multiplier sweep, total P&L, KRW

c	Mean total P&L	Std. total P&L	VaR ₉₅	CVaR ₉₅
0.50	−43,617,209,156	32,187,496,866	121,445,143,908	131,417,052,157
0.75	−49,682,343,643	44,990,807,824	184,328,803,921	195,166,753,028
1.00	−55,747,478,129	59,369,149,552	247,282,335,313	259,001,910,328
1.25	−61,812,612,616	74,415,081,430	310,081,379,678	322,907,477,949
1.50	−67,877,747,102	89,793,641,566	372,580,157,785	386,866,592,247




Figure 7: Total P&L mean and standard deviation as a function of the FX hedge multiplier c .

Within the swept range, both the mean total P&L and its standard deviation are monotonic in c : variance is smallest, and mean P&L least negative, at the smallest tested multiplier $c = 0.5$, and both deteriorate steadily through $c = 1.5$. This shows the natural reference point $c = 1.0$ is neither a risk-minimizing anchor nor even a neutral midpoint: it sits on the costly end of a clear, monotone trade-off, and every step toward a smaller FX multiplier makes the hedge cheaper and less volatile over this range. The mechanism is structural: because c scales the FX notional in lock-step with the WTI delta regardless of the FX leg’s own volatility, correlation, and moneyness, the coupling forces the FX leg to carry more notional than its own risk profile would independently justify once c approaches and exceeds 1.0. The monotone direction is enough to establish that sizing the FX leg as a fixed multiple of the WTI delta is a source of avoidable hedging cost whenever the multiple is not chosen with the two legs’ covariance in mind; the next two subsections turn that direction into the actual minimizer, first within the coupled family (a closed-form, covariance-aware optimal multiplier), then for the instrument-free question of what the FX delta *should* be (the structure’s own analytic FX sensitivity).

7.4 From sweep to minimizer: the closed-form optimal multiplier

The five-point sweep is a sampling of a curve whose exact shape is fixed by the engine's structure. At every rebalancing date the FX position enters the ledger only through $\delta_{FX} = c \cdot \delta_{WTI}$; the WTI leg, the barrier stopping rule, and the early-exercise decision are all computed from the WTI surface alone and are therefore untouched by c (this is why the KO and exercise rates in Table 8 are invariant across the sweep). Consequently the cumulative FX-leg cash flow scales linearly in c path by path, and the per-path hedge cost decomposes affinely:

$$\text{HC}_p(c) = A_p + c B_p, \quad A_p = \text{HC}_p(0), \quad B_p = \text{HC}_p(1) - \text{HC}_p(0), \quad (26)$$

where A_p is the WTI-leg-only hedge cost (FX coupling switched off) and B_p is the unit FX-leg contribution, both recovered from just two engine runs ($c = 0$ and $c = 1$) by per-path differencing. The mean is therefore affine in c with no interior optimum, which is precisely why the swept mean is monotone, and the variance is an exact upward parabola,

$$\mathbb{E}[\text{HC}(c)] = \mathbb{E}[A] + c \mathbb{E}[B], \quad \text{Var}[\text{HC}(c)] = \text{Var}[A] + 2c \text{Cov}(A, B) + c^2 \text{Var}[B], \quad (27)$$

whose unique minimizer is a one-line quotient, structurally Ederington's (1979) univariate minimum-variance hedge ratio, with A as the exposure and the unit FX leg B as the hedging instrument:

$$c^* = -\frac{\text{Cov}(A, B)}{\text{Var}[B]}, \quad \text{Var}[\text{HC}(c^*)] = \text{Var}[A](1 - \rho_{A,B}^2). \quad (28)$$

The swept range $[0.5, 1.5]$ is simply the right arm of this parabola, which is why cost variance rises monotonically across it: the vertex lies to the *left* of the entire tested window.

Two qualifications are essential to reading c^* , and the second is decisive.

The first concerns what is being minimized. In Ederington's setting A is the firm's *spot exposure*. Here $A = \text{HC}_p(0)$ is the WTI leg's own hedge cost, so (27) is the variance of the *hedging programme's ledger* and not of the firm's total position: the importer's physical exposure, \$157,880,000 of monthly dollar settlement against 2,000,000 barrels, appears in neither A nor B . A treasury minimizing total-P&L variance, with the physical exposure written into A , would obtain a different multiplier.

The second is that c^* is not measuring a covariance at all in the ledger that produced it. The WTI hedge is carried as g_1 barrels of futures whose value is $g_1 S_1 S_2$, so *the oil leg already holds $g_1 S_1$ dollars*. A currency leg set to δ_{FX} on top of that leaves the book with a total exchange-rate sensitivity of $g_1 S_1 + \delta_{FX}$, not δ_{FX} . The production ledger never subtracts the first term. Measured on the fitted surface, the unintended position averages roughly four times the structural requirement (31), and the variance minimizer spends itself cancelling it.

The test is decisive. Re-running the sweep with the oil leg's own currency exposure netted out, so that the book's total sensitivity is what δ_{FX} says it is, moves the vertex by

$$c_{\text{gross}}^* = -1.117 \longrightarrow c_{\text{net}}^* = -0.117, \quad (29)$$

a shift of exactly 1.000, and leaves the attainable hedge-cost standard deviation unchanged at KRW 20.32bn. The unit shift is the algebraic signature of the mechanism rather than a coincidence: netting removes precisely one unit of the coupled position, because the oil leg’s currency exposure *is* the $c = 1$ position. The two ledgers are the same book relabeled, which Table 9 shows directly.

ledger	c^*	sd at $c = 0$	sd at $c = 1$	sd at c^*
gross (as shipped)	-1.117	22.80	28.25	20.32
oil-leg FX netted	-0.117	20.34	22.80	20.32

Table 9: The coupling minimizer before and after netting the oil futures leg’s own currency exposure. Hedge-cost standard deviation, KRW billion, 60,000 paths, exercise-consistent ledger. The gross column at c equals the netted column at $c+1$ throughout, and the attainable minimum is identical.

One full unit of the reported multiplier is therefore a bookkeeping correction. What survives once the accidental position is gone is $c^* = -0.117$, and the honest measure of what the optimization buys is its gain over simply not coupling at all: from KRW 20.34bn at $c = 0$ to KRW 20.32bn at c^* , a reduction of 0.14%. The 28% that the same optimization appears to deliver on the gross ledger is, to within a seventh of a percent, the cost of the position the ledger created by accident. An independent adjudication engine that never books the futures leg’s currency term at all returns $c^* \approx 0$ on the same structure, which is the same result reached from the opposite construction.

Section 7.5’s V/S_2 is unaffected, since it is derived analytically rather than from the ledger. The consequence for this paper is that the coupled-family apparatus of Sections 7.3–7.4 should be read as diagnosing a netting error rather than as recovering a covariance-aware hedge ratio, and the recommendation it supports, size the currency leg to V/S_2 , is reached more directly and more robustly from Proposition 1 alone.

Equation (26) is an identity forced by the engine: a third run at $c = 0.5$ reproduces $A_p + 0.5B_p$ path by path with maximum relative error below 10^{-15} . The identity is structural; the economic content sits entirely in where the vertex lands, and on a gross ledger the vertex is the netting artifact. Its location moves with ledger configuration, -0.548 on a to-maturity ledger at 200,000 exact paths (Section 8.3.5) against the -1.117 of Eq. (29), but every gross configuration sits one unit from a netted minimizer that is economically zero, because the unit is the accidental position itself and not a covariance.

The conclusion is the one Section 7.5 reaches analytically: the currency coupling is not a lever on hedge-cost risk. The oil leg dominates $\text{Var}[A]$, no choice of c can touch that part, and once the book is netted correctly the best available c is nothing.

With the netting correction the dynamic result is $c^* \approx 0$: what the currency leg needs is its own small exposure and not a multiple of the oil leg’s.

7.5 What the FX delta should be: the structure’s own analytic sensitivity

The multiplier c^* answers the best-scalar question *within* the coupled family $\delta_{FX} = c\delta_{WTI}$, but a coupled family is itself only one way to size the FX leg, so the deeper question is what the




Figure 8: Hedge-cost standard deviation as the exact parabola $\sqrt{\text{Var}[\text{HC}(c)]}$ implied by the affine decomposition (26). The parabola itself is an identity; its vertex is not the covariance-aware multiplier the figure was originally drawn to display, and lies one unit from zero for the reason Eq. (29) gives.

FX hedge ratio would be if it were not tied to δ_{WTI} at all. For this structure that question has an exact answer. The quanto payoff, its double barrier, and its jump component all act on S_1 alone; the exchange rate S_2 enters only as a multiplicative terminal factor. Writing the option value $V(t) = \mathbb{E}_t^{\mathbb{Q}}[\mathbf{1}\{\tau_{KO} > T\} \max(S_1(T) - K, 0) S_2(T)]$ and separating the S_2 factor by the standard exponential-martingale (quanto) argument,

$$V(t) = S_2(t) g(S_1(t), \text{path-state}, t), \quad (30)$$

exactly linear in $S_2(t)$: the S_2 factor pulls out of the expectation as $S_2(t)e^{(r_{KRW} - r_{US})\tau}$ while the tilt shifts S_1 's drift under $\mathbb{Q}^{KRW}$ by the term $\rho\sigma_1\sigma_2$, which Proposition 1 shows is exactly what the numeraire change removes, and leaves the barrier, the jumps, and (since both continuation and exercise values are linear in S_2) the early-exercise region untouched. Homogeneity of degree one in S_2 gives the structural FX delta in closed form,

$$\delta_{FX}^{\text{struct}}(t) = \frac{\partial V}{\partial S_2} = \frac{V(t)}{S_2(t)}, \quad (31)$$

i.e. the option's true FX exposure is precisely its own USD value, and *not* a scalar multiple of δ_{WTI} times the (far larger) barrel notional a coupled rule sizes it against. This is the analytic root of the sweep's cost: a coupled rule sizes the FX hedge off the WTI hedge notional $\min(S_1, K) \cdot$ barrels, whereas the exposure that actually needs hedging is the option's own carrying value V . Reconciled to a common unit, the coupled family's FX position at $c = 1$ carries a median USD notional of roughly 4.6 times the structural requirement of Eq. (31), which at the reported premium is an option carrying value of about \$22.2M against a coupled position near \$102M. The comparison is stated as a notional ratio rather than a contract count because the ratio is invariant to the futures contract size a given desk trades, while the count

is not: a one-for-one coupling over-hedges the FX leg by roughly $4.6\times$.

Two internal cross-checks accompany this. First, the fitted regression surface provides a second, independent estimate of the same delta, $\partial\tilde{V}/\partial S_2 = (\beta_2 + 2\beta_4 v_2 + \beta_5 v_1)/S_2(0)$, computed from the very coefficients that price the option (Section 5.3); it agrees with the homogeneity form V/S_2 to a median 8.8% over the surface, so the fitted basis respects the structure’s known S_2 -linearity to within that gap and the residual is a measurable property of the five-term polynomial and not of the theorem, which is exact. Second, the structural delta (31) is *positive*, since the option’s KRW value rises with the exchange rate, whereas the variance-minimizing multiplier of Section 7.4 came out *negative*. The two do not disagree. Equation (29) shows the multiplier was negative because it was subtracting a currency position the ledger had created by accident, and once that position is netted the multiplier is essentially zero and the two point the same way. That is what the theory predicts. If V/S_2 is already the right currency exposure, then a correctly-netted book needs no further coupled adjustment, and the minimizer should sit at zero. It does.

7.6 Jump Risk-Premium Re-Pricing Sensitivity

Table 10 and Figure 9 report how the base and stress premiums respond to a pure re-pricing sweep of the risk-neutral jump intensity λ_Q , holding jump-size distribution parameters fixed. This is explicitly *not* a Girsanov jump-measure change; a fully self-consistent jump-measure transformation requires an Esscher transform applied jointly to both the jump intensity and the jump-size distribution to remain risk-neutral, which is outside the scope of the diagnostic reported here.

Table 10: Jump-intensity re-pricing sweep

λ_Q factor	λ_Q (per year)	Base premium	Stress premium
1.00	6.7846	17,188.10	52,507.01
1.25	8.4808	17,743.27	52,263.00
1.50	10.1769	18,207.37	52,234.79
2.00	13.5692	19,009.40	51,974.72

The base premium rises monotonically with λ_Q , as expected: a higher priced-in jump intensity raises the expected cost of a claim exposed to jump risk. The stress premium (computed under the WTI = 113 scenario, with all other inputs at the Table 1 calibration) moves in the opposite direction, falling slightly as λ_Q rises. The direction is consistent with the mechanism: under a deep-stress, near-certainly-ITM scenario the option’s value is dominated by intrinsic value and not optionality, so raising the priced-in jump risk (which primarily inflates the value of the *optionality* component) has a comparatively small, and in this case slightly negative, effect once intrinsic value already dominates the payoff. Note also that this sweep’s own λ_Q -factor-1.0 base premium of KRW 17,188.10 differs from the headline production base premium of KRW 17,132.47 (Section 6.1) by roughly 0.32%, an independently reseeded Monte Carlo draw of the same underlying model, and a useful empirical read on the baseline premium’s own Monte Carlo standard error.




Figure 9: Base and stress premium as a function of the jump-intensity re-pricing factor.

7.7 Jump-Threshold Calibration Robustness

Table 11 and Figure 10 report how the fitted jump parameters, KO rate, and total P&L moments respond to varying the jump-classification threshold k (in multiples of $\sigma\sqrt{dt}$) used by the calibration engine’s threshold-based jump identification heuristic (Section 4), holding the historical return series fixed. This sweep runs on the same jump-adapted exact engine and the same $n = 200,000$ path count as Section 8.3. Its KO-rate column is *not* on the same definition as Section 6.1’s: the calibration sweep re-fits (λ, σ_1) at each threshold and re-prices on a re-struck grid, and the resulting rates (0.171–0.174) are accordingly a factor of roughly 2.5 below the baseline barrier-touch frequency of 0.4369 and cannot be read against it. What the column supports is the *within-sweep* comparison across k , which is the only claim made from it; the same caveat applies to the total-P&L moments in the two right-hand columns, which sit on a different configuration from Table 3 and should likewise be read only across rows.

Table 11: k -sigma threshold robustness sweep

k	λ (per year)	Base premium	KO rate	Mean total P&L	Std. total P&L
2.5	15.714	17,610.40	0.1744	−54,965,034,614	64,303,604,528
3.0	6.7898	17,481.98	0.1727	−56,161,658,548	66,183,065,596
3.5	3.686	17,455.32	0.1711	−54,951,253,711	64,795,934,047

The fitted jump intensity is highly sensitive to k : a looser threshold ($k = 2.5$) classifies more than four times the jump frequency of a tighter one ($k = 3.5$), 15.7 versus 3.7 jumps per year, as diffusive moves get reclassified as jumps. Despite this range in fitted λ , the base premium moves by under 1% and the KO rate stays essentially flat (0.171–0.174), because the calibration resolves the diffusive volatility to compensate for whatever variance the threshold assigns to jumps instead, total variance is conserved across the split, and price and barrier behavior inherit that conservation. The $k = 3.0$ row’s $\lambda = 6.7898$ and the production baseline’s $\lambda = 6.7846$ are the same threshold-count estimator evaluated on samples differing by one observation, $35 \times 252 / 1299$ against $35 \times 252 / 1300$. They are not two independent methods, and their agreement is arithmetic rather than evidential; the informative content of this sweep is the variation *across* k , not the




Figure 10: KO rate and mean total P&L as a function of the jump-classification threshold k .

agreement at $k = 3$.

8 Model Validation and Robustness

8.1 Exact Validation: Closed-Form Drift Bias

The simplest test of the orthogonal Girsanov construction (Section 3.3) compares its closed-form predicted drift bias against the same bias measured directly by simulation, for a family of simple (non-path-dependent, non-barrier) test statistics, across a range of maturities and a range of market-price-of-risk scalings. Table 12 reports the maturity sweep.

Table 12: Closed-form vs. simulated drift bias, by maturity

T (years)	Simulated bias	Theoretical bias	Residual
0.5	-17.5777	-17.5777	7.1×10^{-15}
1.0	-27.6171	-27.6171	3.6×10^{-14}
1.5	-32.2205	-32.2205	2.3×10^{-13}
2.0	-35.7635	-35.7635	2.1×10^{-13}
2.5	-35.0405	-35.0405	-1.1×10^{-13}
3.0	-37.2824	-37.2824	4.3×10^{-14}

An identical result holds when instead sweeping the market-price-of-risk scaling factor from $0.5\times$ to $1.5\times$ the baseline $\mu^{\mathbb{P}}$, with simulated bias again matching the theoretical closed form. Both sweeps confirm the orthogonal Girsanov construction of Section 3.3 is implemented correctly at the level of raw drift moments: this is an exact test in the sense that no discretization error, path-dependent payoff, or barrier feature is involved, only the correctly-orthogonalized first-moment shift itself.

8.2 Inexact Validation: Reweighting the Actual Barrier Payoff

A stronger test reweights genuinely simulated $\mathbb{Q}$ -measure paths, carrying the barrier-monitored KO structure's actual payoff, by the Girsanov likelihood ratio $L(T)$, and compares the resulting

reweighted mean payoff against a direct $\mathbb{P}$ -measure simulation of the same payoff under the true physical drift. Table 13 and Figure 11 report the result.

Table 13: Girsanov reweighting vs. direct simulation, KO payoff

Method	Mean payoff	Std. dev. payoff
Rewighted ($\mathbb{Q}$ -paths $\times$ Girsanov LR)	6,224.31	14,346.47
Direct ($\mathbb{P}$ -measure simulation)	6,217.66	12,782.30
Residual (mean difference)		6.65
Residual (% of direct mean)		+0.11% $\pm$ 0.10




Figure 11: Left: Girsanov-reweighted vs. direct-simulation mean payoff on the actual KO structure. Right: agreement of the corresponding closed-form drift-bias test to within numerical tolerance (Table 12).

The reweighting is run on 200,000 paths over 30 replications with common random numbers, so the two arms share every Brownian increment, jump and bridge draw and differ only in the drift. The residual is +0.11% with a standard error of 0.10% across replications, which places it inside a tenth of a percent of zero. The density that does the reweighting is checked directly on the same runs: $\mathbb{E}[L] = 1.000022$ and $\text{sd}[L] = 0.284216$ against the closed form $\sqrt{e^{\theta^2 T} - 1} = 0.284219$, so the likelihood ratio is a martingale with the variance the construction predicts. A single replication is not informative at this sample size: across the thirty runs the residual ranges from -0.78% to $+1.17\%$, and at $n = 10,000$ its dispersion widens to about three percentage points. The two tests differ in the property that matters: Section 8.1's test statistics are smooth, low-order moments of the underlying diffusion with no discretization-sensitive discontinuity, whereas the KO payoff tested here is a genuinely discontinuous function of the path (it depends on whether a discrete barrier-touch event occurred at all, evaluated on a finite, 217-step Euler—Maruyama discretization of a continuous-time process). Reweighting by a likelihood ratio is a variance-amplifying operation in general (note the reweighted standard deviation (14,346) exceeds the direct standard deviation (12,782) by roughly 12% in Table 13), and that amplified variance, combined with the barrier discontinuity's own discretization error (Section 5.4), is sufficient to produce a residual of this size without any defect in the measure-change construction itself. For a reweighted discontinuous barrier payoff at this sample size, a

residual indistinguishable from zero would itself have warranted scrutiny.

8.3 Exact Simulation, Error Decomposition, and Convergence

The production scheme (Euler steps, whole-step bridge on jump-free steps) carries three approximation layers: diffusion discretization, the bridge’s jump-blindness (Eq. 25), and Monte Carlo noise. This section eliminates the first two and measures all three via a *jump-adapted exact* simulation at $n = 200,000$ paths: Poisson jump times drawn exactly within each step, exact lognormal increments between jumps, per-sub-interval bridge tests, and a direct barrier check at each jump instant, so the path law and its first passage are exact in distribution, with $\mathcal{E}_{\text{jump}} = 0$ by construction.

8.3.1 The jump-gap residual, measured

Evaluating the exact scheme and the production-style test on the *same* paths makes $\mathcal{E}_{\text{jump}}$ measurable path-matched: exact vs. production KO rates are 0.4391 vs. 0.4377 (Q-bank, +0.14pp) and 0.4512 vs. 0.4494 (P-bank, +0.18pp) at 200,000 paths, giving the $O(\Delta t)$ residual as a number and not an order symbol.

8.3.2 Error decomposition and convergence

The error budget of the reported price, source by source, under the exact engine:

- **Time discretization of the path law: eliminated.** Exact lognormal increments between exactly-timed jumps leave no Euler term (formerly strong $O(\Delta t^{1/2})$, weak $O(\Delta t)$).
- **Barrier monitoring: eliminated.** Sub-interval bridges plus jump-instant checks give exact first passage; empirically, the measured KO rate is flat across a 109/217/434/868-step grid refinement (Table 15), so grid-invariance is observed and not assumed.
- **Monte Carlo noise: $O(N^{-1/2})$, measured.** Table 14 reports price, inception delta, and KO rate on nested subsamples of a single 500,000-path bank: every price within two standard errors of every other, standard errors halving on schedule. The inception delta, noisy at 10,000 paths (0.69), settles to 0.544 only from 50,000 paths onward, a direct illustration that Greeks demand far larger samples than prices.
- **Basis truncation: $\leq 1\%$, measured** (Table 16). A strictly larger 10-term cubic moves the price +1.0%; a genuinely non-polynomial exponentially-weighted Laguerre-function basis moves it +0.2%. Two null results are as informative: a degree-2 tensor Laguerre *polynomial* spans the identical six-dimensional space and reproduces the fit, and a payoff-kink (hinge) augmentation $\max(v_1 - 1, 0)$ is also a no-op, because the regression is fitted on in-the-money paths only, where the hinge is linear and already in the span. Basis risk on this surface is a sub-1% effect, and kink-aware bases are redundant *by construction* under ITM-only fitting.
- **Exercise-date density: a contract definition.** With first passage exact, the only remaining step-count effect is the density of Bermudan exercise opportunities (Table 15), the

expected monotone approach to the continuous-exercise limit with shrinking increments. The production contract exercises daily, so 217 dates specify the contract itself.

The full path-count, grid-refinement, and basis-robustness tables underlying this error budget (Tables 14—16) are collected in Appendix A. Against this budget, the production model’s premium of 17,132.47 per unit sits 1.8% below the exact-engine figure at the 500,000-path resolution of Table 14 (17,442.7), and 2.6% below the 217-step row of Table 15 (17,574.2); the spread between those two references is itself the small-sample-plus-grid effect being quantified, the joint size of the Euler, jump-gap, and small-sample effects the production scheme carries, now quantified.

8.3.3 A dual upper bound: the exercise policy is near-optimal

Least-squares Monte Carlo prices are lower bounds: a suboptimal fitted exercise policy can only forfeit value. The pricing model is therefore reported as an *interval*, with the upper end supplied by an Andersen—Broadie dual: the martingale is built from the fitted value surface’s one-period increments (with $\hat{V} = \max(\text{intrinsic}, \text{continuation})$ at every node), each increment’s conditional mean estimated by inner re-simulation. At production resolution (5,000 outer paths, 128 inner paths, and a 44-date exercise skeleton of every fifth trading day plus maturity) the bound is

$$V_0 \in [17,443 \pm 44, \quad 17,885 \pm 59] \text{ KRW per unit}, \quad (32)$$

a measured duality gap of 2.5%. Two opposing approximations shape the upper end: maximizing over a 44-date skeleton understates the full daily-exercise bound, while finite inner sampling biases the estimate *upward* through the convexity of the pathwise maximum, so the 2.5% is a conservative bound indicating that the fitted policy forfeits at most a few percent, not a measurement that it forfeits that amount. On a coarser skeleton (every tenth day, $2,000 \times 64$) the measured gap collapses into its own noise band, consistent with most of the 2.5% being estimator bias and not genuine policy suboptimality. Reporting the interval and not the point is the more informative form of the LSMC price, and everything downstream of the premium (hedge-cost levels, not the coupling comparisons, which are within-engine) inherits an uncertainty of at most this width.

8.3.4 Esscher-consistent jump risk premium

The self-consistent jump risk premium is an Esscher tilt: h maps $(\lambda, \theta_J) \rightarrow (\lambda e^{h\theta_J + h^2\delta_J^2/2}, \theta_J + h\delta_J^2)$ with the compensator recomputed, so every h is genuinely risk-neutral, unlike Section 7.6’s intensity-only diagnostic. Over $h \in \{-0.5, 0, 0.5, 1.0\}$ at 100,000 exact paths, the price spans 17,475 to 17,282 ($\approx 1.1\%$) and the KO rate 0.445 to 0.428: the diversifiable-jump-risk assumption ($h = 0$) is not a knife-edge.

8.3.5 What survives, and what changes, at 200,000 exact paths

On the exact engine at 200,000 paths, the affine identity (26) holds free of the discretization term the production scheme carries, hedge-cost standard deviation at $c = 1$ is KRW 51.90bn,

and the vertex sits at $c^* = -0.548$ with 48.76bn. That vertex is the gross-ledger quantity of Section 7.4: exact simulation removes discretization error, not the netting error, and the two are independent. Classical variance reduction fails structurally: the Merton-series quanto-European control variate (analytic mean 19,316.55 vs. simulated 19,314.12) gains only $\times 1.01$, since KO'd paths zero the option payoff where the control is largest; antithetic pairing gains $\times 1.00$, the payoff being non-monotone in the shocks. On this product, accuracy has to come from path count and not from variance reduction.

9 Discussion

Sections 6—7 expose a tension: the regression delta is *pointwise* noisy (Table 6) yet narrows hedge-cost dispersion on a like-for-like ledger (Section 6.3). The resolution is that pointwise accuracy and hedging performance are different quantities: a proxy delta is correct *for a different option*, one with no barrier. Section 6.3 identifies what the aggregate actually punishes, and it is not barrier-correlated error: a constant hedge ratio carries no barrier information at all, its error is largest near the boundary, and it nonetheless reproduces the fitted surface's entire advantage. What the aggregate punishes is the *level*. Black-76's delta rises toward one as the option goes into the money while a knock-out structure's does not, so a rule that keeps the ratio below Black-76's captures most of the available reduction, whether it obtains that ratio by fitting or by assumption.

This has a direct practical implication for covariance-aware sizing. Coupling $\delta_{FX}(t) = c \cdot \delta_{WTI}(t)$ transmits every property of the WTI-leg delta, both its statistical quality and its cost, directly and mechanically into the FX leg, with no independent check on whether that coupling suits the FX leg's own risk. Section 7.3's finding that cost and variance both rise monotonically with c shows that this transmission is not benign even when the underlying WTI delta is the best available in this paper's suite, the LSMC regression delta of Section 5.3; the same mechanical coupling would plausibly compound into a considerably worse outcome were the underlying WTI delta instead drawn from a barrier-blind closed-form proxy, since a fixed coupling offers no mechanism to contain a poor WTI-leg estimate before it reaches the FX leg. Treating the two legs' deltas as independent, with the FX leg simply tracking the WTI leg one-for-one, is therefore not a safe default under either condition: at best it is a cost paid for operational simplicity, and at worst it is an uncontrolled channel through which WTI-side estimation error is imported directly into the FX hedge.

What the closed-form results of Sections 7.4—7.5 add is that the coupled family is the wrong family, and for a reason that has nothing to do with covariance. A rule of the form $\delta_{FX} = c \delta_{WTI}$ sizes the currency leg off the WTI hedge notional, whereas the exposure that needs hedging is the option's own carrying value V/S_2 : at $c = 1$ the coupling books a median $4.6\times$ what the structure requires. And the multiplier that appeared to correct this within the family was correcting something else. Once the oil futures leg's own currency exposure is netted, the variance-minimizing c falls to -0.117 and buys 0.14% over not coupling at all (Eq. 29). There is no covariance-aware coupling to be had on this structure (Section 7.4).

The recommendation is correspondingly one-part. Size the currency leg to V/S_2 , net of

whatever currency exposure the oil hedge already carries, and do not tune c at all: the parameter has no economic content on a correctly-netted book, and on a gross book the optimizer’s apparent gains are the cost of the accident it is undoing.

For the three audiences that actually run this trade, the findings translate into different operational statements. For the *importer’s treasury*, with the caveat of Section 7.4 that V/S_2 is a property of the option book rather than of the physical purchase programme, the headline is that sizing the FX leg as a fixed positive multiple of the WTI delta increases the option book’s hedge cost without reducing its risk: every additional unit of positively-coupled FX exposure raised both the mean and the variance of realized hedge cost across the entire tested range, so a one-for-one coupling adds exposure under the label of a hedge and not buying a conservative default with premium, on a leg whose true size (the option’s own carrying value, V/S_2) is roughly a factor of four to five smaller than what that coupling books. For the *commodity desk*, the finding with teeth is negative: the fitted regression delta does not beat a barrier-blind closed-form delta once the ledger is made exercise-consistent (Section 6.4), and where it does appear to win, a constant hedge ratio with no barrier information reproduces the win in full (Section 6.3). The operational content is a control rather than a model choice. Before paying for a fitted exercise surface on a knock-out structure, run the constant-delta control and the exercise-consistent ledger; on this structure both of them dissolve the case for the surface. For a *structured-products desk* quoting these notes, the KO-rate decomposition matters commercially: the American engine’s reported knock-out statistic understates the raw barrier-touch frequency by roughly half because early exercise pre-empts the tally, so a desk quoting KO probabilities off engine output without that decomposition would systematically misstate the barrier risk its clients are selling. None of these statements requires adopting this paper’s specific model; each follows from mechanics that survive any recalibration: a coupling rule, a barrier a model cannot see, and a competing stopping time.

10 Limitations

Hedge rebalancing is discrete (daily, 217 steps), interest rates are constant, and the jump-intensity sensitivity of Section 7.6 is a partial measure change bounded by the Esscher-consistent tilt of Section 8.3.4 at $\approx 1.1\%$. Hedge-accounting treatment and static budget allocation are outside the scope. Five boundaries bear on headline numbers and are stated with their measured size.

Estimation risk in the jump block. Jumps are rare, so $(\lambda, \theta_J, \delta_J)$ rest on 35 classified days out of 1,300 returns, the likelihood surface is flat along the intensity-versus-amplitude direction, and the standard errors are correspondingly wide. Section 8.3 controls discretization and Monte Carlo error at a *fixed* parameter vector and says nothing about how well that vector is known. Because the knock-out probability depends on the jump tail, plausible variation within the jump block’s own confidence region would move the KO rate, the premium and the level of hedge cost by more than every numerical residual catalogued here. Read the hedge-cost levels as central estimates inside a wide input-driven band. Propagating the calibration covariance, or integrating over a jump-parameter posterior, is the natural extension.

The estimator's level. Table 6 measures the surface gradient against a finite difference taken with the contract strike held fixed while the spot is bumped; the gap runs from 7.8% at inception to 72.4% near expiry, and Section 7.2 shows the gradient is close to constant over the fitted domain. Comparisons of hedging *rules* on common paths, which is what every headline here is, do not require an accurate $\partial V/\partial S_1$; quoting the gradient as a price sensitivity does, and would be wrong by up to seventy percent late in the option's life. The inception regression is also poorly conditioned, $\text{cond}(X'X) \approx 1.8 \times 10^{10}$, which is why its seed dispersion is 0.077 and why $\partial V/\partial S_2$ is sign-unstable there.

Measure consistency of the production scheme. The engine simulates S_1 with drift r_{US} , S_2 with drift $r_{KRW} - r_{US}$, and discounts the won payoff at r_{US} . Proposition 1 gives the correctly specified value, against which this combination carries a spurious $e^{(r_{KRW}-r_{US})T} \approx -0.42\%$ and a spurious $\rho\sigma_1\sigma_2$ drift tilt worth about $+1\%$; the net is $+0.4\%$ at the calibrated correlation, below the 1.8% discretization residual, but $+5.3\%$ at $\rho = 0.5$. Any use of this engine at a materially different correlation should re-derive the drift from (14).

What the hedge-cost comparison can support. Table 3's three engines differ in payoff, premium and stopping time as well as in delta rule, so its raw gap is not attributable to delta quality; Section 6.3 gives the controlled comparison and the constant-ratio control. The tri-modality of Section 6.5 is resolved at a default kernel bandwidth and collapses at wider ones; no dip test is offered.

Ledger scope. Every hedge-cost figure here is the variance of the option-hedging ledger, in which the importer's physical dollar purchase appears nowhere. Section 7.4's netting correction is internal to that ledger: it removes the currency exposure the oil futures leg carries against the option, not the exposure of the physical purchase programme. A treasury minimizing total-position variance, with the physical leg written in, faces a different optimization than the one solved here, and its answer for the currency leg would be a genuine positive exposure rather than the V/S_2 of the option book alone. The recommendation of this paper is scoped to the derivative book.

Subject to these boundaries, the paper's findings are comparative statements made on a common path bank and a common parameter vector, and are for that reason more robust to input uncertainty than the absolute levels: they turn on the factorization of (14), on the shape of the fitted surface, and on the structural mismatch between a barrier-free model and a barrier-carrying instrument.

11 Conclusion

This paper set out to derive a covariance-aware hedge ratio for the currency leg of a barrier oil option, and found instead that the coupling it was built on is not where the economics sit.

What holds is analytic. A change of numeraire factorizes the payoff into the spot rate times a dollar option, so neither the price nor either delta depends on the correlation between the legs (Proposition 1), and homogeneity then fixes the currency delta at the option's own carrying value V/S_2 (Section 7.5). The per-path affine decomposition of hedge cost in the coupling parameter is likewise an identity, reproduced to machine precision, and the knock-out

rate partition into exercise, barrier and survival is a measured property of the path bank.

What does not hold is the empirical apparatus built on top. The fitted regression surface is close to a constant over its fitted domain and carries almost none of the state dependence a barrier delta requires (Section 7.2); its advantage over a closed-form proxy is reproduced by a constant hedge ratio (Section 6.3) and reverses outright once the ledger is made exercise-consistent (Section 6.4); and the negative coupling multiplier is a correction for currency exposure the oil futures leg already carries, vanishing to within noise when that exposure is netted (Section 7.4).

Two of these are worth stating as prescriptions rather than as findings about one structure. A claim that a fitted exercise surface delivers barrier-aware hedging should be required to beat a constant-delta control before it is accepted. And a hedge ledger that carries a futures leg in a foreign currency must net that leg’s own currency exposure before any currency-leg optimization is run, or the optimizer will spend itself undoing an accident.

A Convergence and Basis-Robustness Tables

These tables support the error budget of Section 8.3.2: path-count convergence, exercise-grid refinement, and regression-basis robustness, all on the jump-adapted exact engine of Section 8.3.

Paths N	Price (KRW/unit)	s.e.	$\delta_{WTI}(0)$	KO rate
10,000	17,298.5	196.6	0.692	0.4340
50,000	17,414.9	88.4	0.547	0.4395
100,000	17,394.0	62.5	0.544	0.4391
200,000	17,468.5	44.4	0.543	0.4397
500,000	17,442.7	28.0	0.545	0.4397

Table 14: Path-count convergence on nested subsamples of one 500,000-path jump-adapted exact bank: price with standard error, inception regression delta, and exact-first-passage KO rate.

Steps (exercise dates)	Price (KRW/unit)	s.e.	KO rate
109	17,141.4	86.0	0.4403
217	17,574.2	88.9	0.4398
434	17,702.0	91.6	0.4395
868	17,812.3	93.8	0.4395

Table 15: Grid refinement at 50,000 exact paths per row. The KO rate is grid-invariant (first passage is exact at every grid); the price rises with shrinking increments purely through Bermudan exercise-date density.

Regression basis	Price	vs. poly-6	Note
Polynomial, 6-term (production)	17,468.5	—	
Hinge-augmented, 9-term	17,468.5	$\pm 0.00\%$	no-op: hinge linear on ITM set
Laguerre functions, 6-term	17,502.5	$+0.19\%$	non-polynomial span
Cubic, 10-term	17,638.7	$+0.97\%$	strictly larger space

Table 16: Basis robustness at 200,000 exact paths (same bank as Table 14); prices in KRW/unit. The Laguerre row uses $e^{-x/2}$ -weighted Laguerre functions, a genuinely different function space.

B Proof of the American Extension of Proposition 1

Let $N(t) = S_2(t)e^{r_{US}t}$, the KRW value of the USD money-market account, a traded KRW asset with $N(0) = S_2(0)$. Its discounted price $Z_t := N(t)e^{-r_{KRW}t}/N(0)$ is a positive $\mathbb{Q}^{KRW}$ -martingale with $Z_0 = 1$, and defines the measure change $d\mathbb{Q}^{US}/d\mathbb{Q}^{KRW}|_{\mathcal{F}_t} = Z_t$. For any stopping time $\tau \leq T$ and any $\mathcal{F}_\tau$ -measurable payoff, optional stopping applied to Z gives the abstract Bayes identity $\mathbb{E}^{KRW}[Z_\tau Y] = \mathbb{E}^{US}[Y]$, so

$$\mathbb{E}^{KRW}[e^{-r_{KRW}\tau} X_\tau S_2(\tau)] = \mathbb{E}^{US}\left[\frac{e^{-r_{KRW}\tau} X_\tau S_2(\tau)}{Z_\tau}\right] = S_2(0) \mathbb{E}^{US}[e^{-r_{US}\tau} X_\tau],$$

since $e^{-r_{KRW}\tau} S_2(\tau)/Z_\tau = S_2(0)e^{-r_{US}\tau}$ identically. Equivalent measures share null sets and hence the same family of $\mathcal{F}$ -stopping times, so taking suprema on both sides gives $V^{\text{Am}}(0) = S_2(0) \sup_\tau \mathbb{E}^{US}[e^{-r_{US}\tau} X_\tau]$. Finally, the optimand $e^{-r_{US}t} X_t$ is adapted to the sub-filtration $\mathcal{F}^{S_1}$ generated by the S_1 path and its barrier state; conditioning any $\mathcal{F}$ -stopping rule down to $\mathcal{F}^{S_1}$ by the tower property leaves the value of the $\mathcal{F}^{S_1}$ -Snell envelope unchanged, so the supremum is attained on $\mathcal{F}^{S_1}$ -stopping times and the exercise region is S_1 -measurable, free of ρ and σ_2 . $\square$

C The Jump-Classification and Moment-Matching Construction

Each daily return $r_i = \ln(S_1(t_i)/S_1(t_{i-1}))$ is classified as a jump day when it exceeds a robust k -sigma band around a robust location estimate of the return series, at the production threshold $k = 3$; classified days split by sign into the up and down regimes. Within each regime the intensity is the annualised count, $\lambda_r = n_r \cdot 252/N$; the jump mean $\theta_{J,r}$ and dispersion $\delta_{J,r}$ are the sample moments of the classified returns; and the diffusive σ_1 is re-estimated from the unclassified remainder, so the observed quadratic variation is split between components and never duplicated, the identification discipline Section 4 requires. At $k = 3$ on the 1,300-return sample this yields $n_{up} = 12$, $n_{dn} = 23$, $\lambda = 35 \times 252/1300 = 6.7846$, and the regime moments of Table 1; Section 7.7 sweeps $k \in \{2.5, 3.0, 3.5\}$, which measures the estimator's sensitivity to the one tuning constant it has.

For clarity about what the estimator is not: it is a hard classification followed by moment matching, not an expectation-maximization fit. No posterior membership weights are computed and no likelihood is ascended; a genuine Poisson-mixture likelihood would weight every return partially into every component. The hard-threshold construction is used because jump days at these intensities are sparse enough that classification is nearly deterministic, and because the sensitivity that matters, the dependence on k , is measurable directly rather than integrated out.

Code and data availability. Every engine, the frozen derived inputs, and the scripts that regenerate each table and figure in this paper are available at github.com/JihongParker/wti-fx-hedge-program.

References

- [1] Adler, M., and B. Dumas (1984). “Exposure to Currency Risk: Definition and Measurement.” *Financial Management* 13(2), 41—50.
- [2] Anderson, R. W., and J.-P. Danthine (1981). “Cross Hedging.” *Journal of Political Economy* 89(6), 1182—1196.
- [3] Black, F. (1976). The pricing of commodity contracts. *Journal of Financial Economics*, 3(1—2), 167—179.
- [4] Broadie, M., & Glasserman, P. (1996). Estimating security price derivatives using simulation. *Management Science*, 42(2), 269—285.
- [5] Broadie, M., Glasserman, P., & Kou, S. G. (1997). A continuity correction for discrete barrier options. *Mathematical Finance*, 7(4), 325—349.
- [6] Cont, R., & Tankov, P. (2004). *Financial Modelling with Jump Processes*. Chapman & Hall/CRC.
- [7] Ederington, L. H. (1979). The hedging performance of the new futures markets. *Journal of Finance*, 34(1), 157—170.
- [8] Garman, M. B., & Kohlhagen, S. W. (1983). Foreign currency option values. *Journal of International Money and Finance*, 2(3), 231—237.
- [9] Longstaff, F. A., & Schwartz, E. S. (2001). Valuing American options by simulation: a simple least-squares approach. *The Review of Financial Studies*, 14(1), 113—147.
- [10] Merton, R. C. (1976). Option pricing when underlying stock returns are discontinuous. *Journal of Financial Economics*, 3(1—2), 125—144.
- [11] Musiela, M., & Rutkowski, M. (2005). *Martingale Methods in Financial Modelling* (2nd ed.). Springer.
- [12] Reiner, E. (1992). Quanto mechanics. *Risk*, 5(3), 59—63.
- [13] Turnbull, S. M., & Wakeman, L. M. (1991). A quick algorithm for pricing European average options. *Journal of Financial and Quantitative Analysis*, 26(3), 377—389.